

GEOTECHNICAL  
REPORT NO. 24-99

PROJECT PR SHIL 302 (1)  
FELLOH NATIONAL MILITARY PARK  
HARDIN COUNTY, TENNESSEE

FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA  
July 2000

## TABLE OF CONTENTS

<b><u>REPORT</u></b>	<b><u>PAGE</u></b>
<b>INTRODUCTION</b>	
General .....	1
Project Description .....	1
Regional Geology .....	3
<b>PROCEDURES AND RESULTS</b>	
Pavement Condition Survey .....	4
Soil Borings .....	4
Sampling .....	4
Field Tests and Measurements .....	4
Data Summary .....	4
Laboratory Investigation .....	5
Findings .....	5
<b>ANALYSIS AND CONCLUSIONS</b>	
Pavement .....	12
Foundations .....	12
<b>RECOMMENDATIONS</b>	
Pavement .....	13
Foundations .....	16
<b>DISCLAIMER / LIMITATIONS .....</b>	
<b>17</b>	
<b>APPENDICES</b>	
<b>APPENDIX A - Figures</b>	
<b>APPENDIX B - Boring Location Plan</b>	
<b>APPENDIX C - Boring Logs</b>	
<b>APPENDIX D - Laboratory Data</b>	
<b>APPENDIX E - Boring Summary</b>	
<b>APPENDIX F - RPCC Pavement Condition Survey</b>	
<b>APPENDIX G - Pavement Design</b>	
<b>APPENDIX H - Allowable Bearing Capacity and Settlement Calculations</b>	

**Note: Design changes subsequent to publication of this report and prior to project advertisement will be documented by a memo inserted after the title page.**



**GEOTECHNICAL  
REPORT NO. 24-99**

**PROJECT PRA SHIL 502 (1)  
SHILOH NATIONAL MILITARY PARK  
HARDIN COUNTY, TENNESSEE**

**INTRODUCTION**

**General**

This report presents the results of the geotechnical investigation for Project SHIL 502 (1) located at Shiloh National Military Park in Harding County, Tennessee. The project involves rehabilitation and reconstruction of 14.7 km of the park roads, parking areas, turnarounds and replacement of a small bridge with a bottomless structural plate pipe-arch culvert. A Project Location Map and Project Vicinity Map are presented in Appendix A.

**Project Description**

***Brown's Landing Road (NPS Route 502)***

Brown's landing road will be widened to accommodate two-way traffic from Hamburg-Savannah road to the Indian Mound palisades near the vicinity of the 17<sup>th</sup> Kentucky Infantry Monument. A new parking area and turnaround will be reconstructed at the Indian Mound palisades.

***Pittsburg Landing Road I (NPS Route 13)***

Pittsburg Landing road I and turnouts will be overlaid with hot asphalt concrete pavement (HACP). The road will be relocated beginning east of Chambers Field and terminating near the front gate of the cemetery. Two concrete pads will be constructed for the vista off of Brown's Landing Road overlooking Pittsburg landing road.

The section of the maintenance service road extending between the existing and proposed Pittsburg Landing road I alignment at approximate station 21+360 will be reconstructed.

***Visitor Center and Cemetery Parking Areas***

The existing main visitor center and cemetery parking areas will be reconfigured and reconstructed.

***Pittsburg Landing Road II***

The retaining wall will be removed and a bus and 2-car turnaround will be constructed. The remaining portion of the road will be overlaid with HACP.

### ***Reconnoitering Road (NPS Route 500)***

Reconnoitering road will be overlaid with HACP. The existing bridge on Reconnoitering road is 4.0 m long and 5.5 m wide bridge span that will be replaced with a bottomless structural plate arch pipe 4.4 m long by 9.5 m wide in order to accommodate a travel lane and a pedestrian and bike sidewalk.

### ***Corinth-Pittsburg Landing Road (NPS Route 12)***

Corinth-Pittsburg is currently a reinforced portland cement concrete (RPCC) paved road. The RPCC pavement will be rehabilitated including cleaning and sealing of the transverse and longitudinal joints and repairing of the transverse cracks.

### ***New Entrance Road***

A new entrance road will be constructed from Pittsburg landing road I to Corinth-Pittsburg landing road on an existing surface treated road.

### ***McClernand Road***

A portion of McClernand road will be overlaid with HACP and a portion will be realigned.

### ***Eastern Corinth road I (NPS Route 14)***

Eastern Corinth road will be overlaid with HACP between station 10+000 and 11+115 during this phase of the project the remainder of this road will be rehabilitated under a future project. It's intersection with Peabody Road and Bark Road will be reconfigured.

### ***Peabody Road (NPS Route 501)***

Peabody road will be overlaid with HACP. The gravel tour stop area located left of station 11+000 will be reconstructed.

### ***Hamburg-Savannah Road (NPS Route 11)***

Hamburg-Savannah road will be overlaid with HACP. The two-car turnout right of station 11+330 ± will be paved. Rehabilitation of the following parking areas and roadway located off of Hamburg-Savannah road will be performed.

### ***New One-way Loop Around Tent Hospital Site***

A new one-way loop will be constructed from station 10+050 to a dirt road along the northeast park's boundary then back to the Tent Hospital site access road.

### ***Johnston Memorial***

Johnston memorial will be overlaid with HACP. A two-bus turnout will be constructed to the northeast of the existing loop.

### ***Peach Orchard Parking Area***

The northern end of the parking will be widened to improve accessibility for the buses.

### ***Bloody Pond Tour Stop***

The roadway and the two turnouts at Bloody Pond tour stop will be reconstructed.

## **Regional Geology**

The project site is located within the Gulf Coastal Plain physiographic province. The majority of the project site is underlain by high-level alluvial deposits which consist of iron stained gravel, sand, silt and clay; variable in thickness but generally less than 18 m thick. Alluvial deposits and the Coffee Sand formations underlie the site in the flood plain areas parallel to the Tennessee River. The alluvial deposits consist of sand, silt, clay and gravel and range in thickness between 6 m to more than 30 m. The Coffee Sand formation consists of loose fine-grained sand, light-gray, glauconitic, micaceous; interbedded with laminated lignitic clay. The thickness of the Coffee Sand formation varies between 7 and 61 m.

The majority of the near-surface soils at the site are of the Paden-Pickwick-Waynesboro association. This association consists of moderately well drained soils and well drained soils on high terraces. Paden and Pickwick soil series make up about 70 percent of the association. The surface layer is loam and silt loam. The subsoil is chiefly silty clay loam and clay loam. The Waynesboro series consists of fine sandy loam and gravelly sandy loam. The near-surface soils adjacent to the Tennessee River are of the Wolfcreek-Beason-Egam association. This association consists of nearly level soils on low stream terraces and flood plains of the Tennessee River. The surface layer consists of dark grayish-brown to brown silt loam and varies in depth between 0.45 and 0.8 m. The substratum is brown or yellowish-brown silt loam with varying amounts of chert.

## **PROCEDURES AND RESULTS**

The field investigation for this project consisted of a generalized pavement condition survey and a subsurface exploration program. General procedures used during performance of the field investigations are expounded as follows:

## **Pavement Condition Survey**

Pavement condition surveys were conducted by Eastern Federal Lands Highway Division (EFLHD) geotechnical personnel during August, 1996 and August 1999. The pavement condition surveys were conducted in general accordance with the "Distress Identification Manual for the Long-Term Pavement Performance Project (SHRP-P-338)". The purpose of the pavement condition surveys was to make a preliminary determination of the types and limits of the different reconstruction or rehabilitation techniques that would be required based on the type, severity and extent of pavement distress.

## **Soil Borings**

The subsurface exploration program was conducted by EFLHD geotechnical personnel during August 1996, consisting of sixty six borings. Borings were drilled using a trailer-mounted CME 45 drill rig. Approximate locations of each boring are shown on the Boring Location Plans in Appendix B. Borings were advanced using hollow-stem augers to depths ranging from 1.35 to 4.98 meters. Pavement cores were obtained at 11 locations.

## **Sampling**

Sampling of materials beneath the tip of the hollow-stem augers was performed in each boring through the auger stem as the borings were advanced. Representative soil samples were retrieved using 50 mm outside diameter split-barrel sampler in accordance with AASHTO T200-87. Sampling was typically conducted continuously to the termination depth of all borings. Representative portions of split-spoon samples were preserved in glass jars for laboratory testing. Additionally, five bulk samples of auger cuttings were collected from Borings VC-6, R-2, RS-3, T-4 and BL-3. The sampling sequence and associated jar and bag samples for each boring are presented on its appropriate Boring Log in Appendix C.

## **Field Tests and Measurements**

The following field tests and measurements were performed by exploration personnel during the course of the subsurface exploration. Boring locations were determined from features present on site. Standard penetration tests (SPT) were performed and resistance was recorded during the recovery of each split barrel sample, in accordance with AASHTO T206-87. The sampler was driven into the soil using an automatic hammer. Sample recovery measurements were made and recorded for each sampling attempt. Asphalt and base thickness were measured for each pavement encountered. The relative consistency of each cohesive soil sample was estimated using a calibrated pocket penetrometer. A field description by color and texture was made for each recovered soil sample. The depth of groundwater, if present, was measured at the time of completion of each boring, and again prior to backfilling the boreholes.

## **Data Summary**

The results of the field tests and measurements were recorded on the drillers logs and appropriate

data sheets in the field. These data sheets and logs contain information concerning the boring methods; samples attempted and recovered; indications of the presence of various materials such as gravel, pebbles, organic matter, etc. They also contain interpretations by the exploration foreman of the conditions between samples based on the performance of the equipment and cuttings brought to the surface by the drilling tools. Therefore, the field data represents both factual and interpretative information.

The Boring Logs in Appendix C of this report represent a compilation of field and laboratory data and descriptions of the soil and rock samples by a geotechnical engineer. Occasionally, these records do not include all data recorded on driller's logs and field data sheets, but do include all information considered relevant to the design and construction of this project.

### **Laboratory Investigation**

At the conclusion of the field work, laboratory testing was conducted on select representative soil samples. Laboratory tests included gradation (AASHTO T-27), Atterberg limits (AASHTO T-89, T-90), classification (AASHTO T-317) and moisture content (AASHTO T-265). Five bulk samples from Borings VC-6, R-2, RS-3, T-4 and BL-3 were tested for the California Bearing Ratio (AASHTO T-193) and Standard Proctor tests (AASHTO T-99), including maximum dry density and optimum moisture content. The results of the laboratory tests on the jar and bulk samples are presented in Appendix D. The results of the laboratory tests on the bulk samples are summarized in Table 1.

**TABLE 1 - BULK SAMPLES LABORATORY TEST DATA**

<b>Boring No.</b>	<b>AASHTO Classification</b>	<b>Liquid Limit</b>	<b>Plasticity Index</b>	<b>Percent Fines</b>	<b>Optimum Moisture Content %</b>	<b>Maximum Dry Density (kN/m<sup>3</sup>)</b>	<b>CBR</b>
BL-3	A-4	25	6	57	10.7	19.1	11
PLI-3	A-6	35	18	83	14.0	18.4	7
VC-6	A-7-6	48	29	77	16.3	17.9	6
R-2	A-7-6	50	26	44	13.8	18.5	8
RS-3	A-6	29	11	--	15.8	18.1	8
T-4	A-7-6	31	13	74	11.3	19.46	7

### **Findings**

Findings for each site are described below. A summary of the pavement borings is listed in Tables D-1 through D-5 in Appendix D. Included in those tables are the existing AC, RPCC (where present) and aggregate base thicknesses and subgrade material classification encountered at each boring.

### ***Brown's Landing Road (NPS Route 502)***

Borings BL-1 through BL-3 were drilled at offset locations from the roadway pavement for the proposed widening of Brown's Landing road. Borings BL-4 and BL-5 were drilled for the proposed parking lot and turnaround at Indian Mound palisades in the vicinity of the 17<sup>th</sup> Kentucky Infantry Monument.

Brown silty clay with some sand and trace of chert (A-4, A-6) was encountered in all borings. A brown silty sand with trace of chert layer was encountered to a depth of 0.61 m in Boring BL-1 (A-2-4). Moisture contents varied from 3.7 to 26.3%. Liquid limit ranged from 42 to 52, plasticity indices from 12 with 18 and 48 to 61% fines. Standard Penetration Test (SPT) resistances encountered within the silty clay ranged from 3 to 19 blows per 300 mm suggesting soft to very stiff consistencies. Laboratory test results for the Bulk sample are presented in Table 1.

The pavement generally contains low to moderate severity fatigue and longitudinal cracking at a few locations between the intersection of Browns Landing and Eastern Corinth roads and the Indian Mounds palisades.

### ***Pittsburg Landing Road I (NPS Route 13)***

The AC thickness encountered in Borings PLI-1 through PLI-5 varied between 70 to 110 mm overlaying 40 to 120 mm of aggregate base.

Red and brown clay with varying amounts of silt and traces of sand (A-6) was encountered in all borings. Laboratory test results indicate moisture contents between 12.0% and 20.3%, liquid limits between 28 and 39, plasticity indices between 12 and 22 with 40.7% to 82.9% fines. SPT resistances encountered ranged from 5 to 25 blows per 300 mm suggesting medium stiff to very stiff consistencies. Borings PLI-9, PLI-10 and PLI-11 were drilled in the proposed relocation section of the road east of Chambers Field to the Visitor and Cemetery parking areas. Laboratory test results for the bulk samples are presented in Table 1. Four pavement cores were obtained from Borings PLI-6 through PLI-8 and PLI-12.

The pavement generally contains low to moderate fatigue cracking at a few locations within the roadway.

Boring V-1 was drilled for the vista off Brown's Landing road. Brown silt with trace sand, clay and chert (A-4) was encountered to the termination depth of 2.95 m. Laboratory test results indicate a natural moisture content of 18.5%, a liquid limit of 32, non-plastic plasticity index and 85.0% fines. SPT resistances varied from 3 to 81 blows per 300 mm indicating soft to hard consistencies.

Boring S-1 was drilled in the maintenance service road between the existing and proposed Pittsburg Landing road I alignments. The AC thickness encountered in Boring S-1 was 90 mm underlain by 100 mm aggregate base.

Beneath the pavement, brown clay with trace silt and sand (A-7-6) was encountered to the termination depth of 1.52 m. Laboratory test results indicate a natural moisture content of 15.4%, a liquid limit of 45, a plasticity index of 27 and 90.4% fines. SPT resistances ranged from 32 to 39 blows per 300 mm indicating hard consistency.

### ***Visitor Center and Cemetery Parking Areas***

The AC thickness encountered in Borings VC-1 through VC-6 varied between 70 to 130 mm overlaying 90 to 220 mm of aggregate base.

Brown and red clay and silty clay with trace to some fine to medium sand (A-6) was encountered in all borings. Laboratory test results indicate a natural moisture content of 9.3%, a liquid limit of 30, a plasticity index of 6 with 38.4% fines. SPT resistances encountered ranged from 5 to 38 blows per 300 mm indicating medium stiff to hard consistencies.

The pavement generally contains low to moderate severity fatigue and longitudinal cracking at a few locations within the parking area.

### ***Pittsburg Landing Road II***

The AC thickness encountered in Borings PLII-1 through PLII-3 varied between 70 and 90 mm overlaying 70 to 120 mm of aggregate base.

Beneath the pavement in Boring PLII-3, fill and/or disturbed soils consisting of silty sand and clay with trace of chert (A-2-4) were encountered to a depth of 1.52 m. Laboratory test results indicate natural moisture content ranged from 11.3% to 11.8%, liquid limits from 21 to 24, a non-plastic plasticity index with 25.5 to 27.3% fines. SPT resistances encountered within the fill varied from 3 to 7 blows per 300 mm, generally suggesting very loose to loose conditions.

Red and brown clay with varying amounts of silt (A-4) was encountered to the termination depth of Borings PLII-1, PLII-2 and below the fills in Boring PLII-3. Laboratory test results indicate natural moisture contents ranged from 12.4% to 18.2%, liquid limits from 32 to 34, plasticity indices from 15 to 17 and 82.6 to 85.0 percent fines. SPT N-values ranged from 6 to 13 blows per 300 mm, generally indicating medium stiff to stiff consistencies.

The pavement generally contains low severity fatigue and block cracking.

### ***Reconnoitering Road***

The AC thickness encountered in Borings R-1 through R-3 was 80 mm overlaying 60 to 70 mm of aggregate base.

Beneath the pavement, reddish brown and brown clay with some silt and trace fine sand (A-7-6) was encountered to the termination depth of all borings. Laboratory results indicate natural moisture contents ranged from 17.2% to 18.8, liquid limits from 47 to 48, plasticity indices from

22 to 26 with 79.4 to 85.4% fines. SPT resistances encountered ranged from 9 to 29 blows per 300 mm suggesting stiff to very stiff consistencies.

The pavement generally contains minimal low severity fatigue and longitudinal cracking.

### ***Bridge Replacement on Reconnoitering Road***

Borings BB-1 and BB-2 were drilled for the foundations of the replacement bridge/culvert. Brown and gray silty sand and sand with trace weathered rock fragments and clay (A-2-4) was encountered to a depth of 2.54 m in Boring BB-1 and to the bottom of Boring BB-2. SPT resistances varied between 2 to 30 blows per 300 mm indicating very loose to medium dense conditions. In Boring BB-2, a high SPT resistance of 65 blows per 300 mm was encountered at an approximate depth of 2.0 m. This high SPT resistance is suspected to be because a random boulder was encountered and is not representative of the general subsurface conditions.

Beneath the sands in Boring BB-1, brown and gray silty clay with trace sand (A-7-6) was encountered to the termination depth of 4.98 m. Laboratory test results indicate a natural moisture content of 38%, a liquid limit of 71, a plasticity index of 44 with 90.0% fines. SPT resistances varied from 2 to 6 blows per 300 mm suggesting very soft to medium stiff consistencies.

### ***Corinth-Pittsburg Landing Road***

RPCC thickness in Borings CP-1 through CP-12 varied between 120 to 160 mm. No aggregate base was encountered in any of the borings.

Beneath the pavement in Borings CP-1 through CP-6 and CP-10, brown and gray silty clay with trace of sand, chert and gravel (A-6) was encountered to the termination depth of the borings. Laboratory test results indicate natural moisture contents ranged from 11.6% to 24.9%, liquid limits from 33 to 37, plasticity indices from 15 to 17 with 77.8% to 88.1% fines. SPT resistances encountered ranged from 6 to 29 blows per 300 mm suggesting medium stiff to very stiff consistencies.

Gray and brown silty sand with trace to some clay and trace gravel (A-2-4, A-4) were encountered to the termination depths of Borings CP-7 through CP-9, CP-11 and CP-12. Laboratory test results indicate natural moisture contents ranged from 13.2 to 27.5%, liquid limits from 18 to 27, plasticity indices from non-plastic to 11 with 30.8 to 59.2% fines. SPT resistances encountered ranged from weight of hammer (WOH) to 21 blows per 300 mm suggesting very loose to medium dense conditions.

Corinth-Pittsburg Landing road consists of approximately 862 RPCC slabs (431 slabs in each direction) typically 12.2 m long by 3.0 m wide. Low to high severity transverse and longitudinal cracks, corner breaks, spalling and blow outs were observed within 33% of the RPCC slabs and slab joints. The slab number and type of distress observed are listed on Table 1 in Appendix F.



### ***New Entrance Road***

The thickness of the asphalt surface treatment course encountered in Borings E-1 and E-2 varied from 30 to 40 mm overlaying 40 to 130 mm of aggregate base.

Beneath the pavement, brown and reddish brown clay with trace silt and sand (A-6, A-7-6) were encountered to the termination depths of the borings. Laboratory test results indicate natural moisture contents ranged from 20.1 to 21.9%, liquid limits from 40 to 48, plasticity indices from 19 to 26 and 69.4 to 84.0% fines. SPT resistances encountered ranged from 2 to 15 blows per 300 mm indicating very soft to stiff consistencies.

The pavement contains several 25 to 75 mm deep ruts and settlement.

### ***McClermand Road***

The AC thickness encountered in Borings MS-1 through MS-5 varied from 30 to 100 mm with an average thickness of 75 mm. No aggregate base was encountered underlying the AC.

Beneath the pavement, brown and reddish brown clay and silty clay with trace sand (A-6) was encountered to the termination depth of all borings. Laboratory test results indicate natural moisture contents ranged from 17.0% to 25.8%, liquid limits from 32 to 39, plasticity indices from 14 to 18 and 90.5% to 97.1% fines. SPT resistances encountered ranged from 2 to 22 blows per 300 mm indicating very soft to very stiff consistencies.

### ***Eastern Corinth Road I (NPS Route 14)***

The AC thickness encountered in Borings EC-1 through EC-3 varied from 90 to 110 mm overlaying 100 to 140 mm aggregate base.

Beneath the pavement, brown clay with some silt and trace sand (A-6, A-7-6) was encountered to the termination depth of all borings. Laboratory test results indicate natural moisture contents varied from 14.1% to 19.4%, liquid limits from 37 to 45, plasticity indices from 17 to 27 and 68.0% to 87.9% fines. SPT resistances encountered ranged from 9 to 16 blows per 300 mm indicating stiff to very stiff consistencies.

The results of the pavement condition survey for Eastern Corinth Road I are listed in Table 2.

**TABLE 2 - PAVEMENT DISTRESS - EASTERN CORINTH ROAD I**

<b>Approximate Stations</b>	<b>Severity and Type of Pavement Distress <sup>1)</sup></b>
10+000 to 10+150	L to H fatigue and longitudinal cracking, full lane
10+175 to 10+290	M to H fatigue, block and cracking, 25 to 75 mm ruts, full lane

Approximate Stations	Severity and Type of Pavement Distress <sup>1)</sup>
10+650 to 10+670	M fatigue cracking, raveling and potholes, SB lane, full
10+685 to 10+710	H raveling and M longitudinal, full
10+820 to 10+850	L fatigue and longitudinal, full
10+950 to 10+970	L fatigue and raveling, full
11+082	H transverse cracking
11+088 to 11+095	H fatigue, full

1) L, M, H = Low, Moderate and High Severity

### ***Peabody Road (NPS Route 501)***

The AC thickness encountered in Borings RS-1 through RS-3 and pavement cores RS-4 through RS-5 varied from 70 to 160 mm with an average thickness of 112 mm. The aggregate base thickness varied from 0 to 140 mm.

Beneath the pavement, brown silty clay and sandy clay (A-6, A-7-6) were encountered to the termination depth of all borings. Laboratory test results indicate natural moisture contents ranged from 15.2% to 22.2%, liquid limits from 29 to 41, plasticity indices from 11 to 19 and 57.9% to 95% fines. SPT resistances varied from 3 to 18 blows per 300 mm indicating soft to very stiff consistencies.

The pavement generally contains low severity fatigue cracking at a few locations.

### ***Hamburg-Savannah Road (NPS Route 11)***

The AC thickness encountered in Borings HS-1 through HS-4 varied from 60 to 90 mm with an average thickness of 75 mm. No aggregate base was encountered.

Beneath the pavement, brown clay and silty clay with trace to some sand was encountered to the termination depth of all borings. SPT resistances varied from 3 to 34 blows per 300 mm indicating soft to hard consistencies.

The pavement generally contains low to medium severity fatigue, longitudinal and block cracking at several locations within the roadway. High severity transverse cracking was encountered between approximate stations 10+600 and 10+650 at 10 m intervals.

### ***Johnston Memorial***

Brown silty sand with trace chert and clay (A-4) was encountered in Boring J-1 to the termination depth of 2.74 m. Laboratory test results indicate a natural moisture content of 6.9%, liquid limit of 36, non-plastic plasticity index and 49.3% fines. SPT resistances varied

from 16 to 100+ blows per 300 mm indicating very stiff to hard consistencies.

Two cores (J-2 and J-3) were retrieved from the parking area. The AC thickness encountered in these cores ranged from 70 to 90 mm with no aggregate base.

The pavement generally contains high severity fatigue and block cracking and potholes in the area surrounding the monument and near the exit from the parking area.

### ***Peach Orchard Parking***

The AC thickness encountered in Borings PO-1 and PO-2 varied from 60 to 70 mm with no aggregate base.

Beneath the pavement, brown clay with some silt and trace sand (A-6) was encountered to the termination depth of both borings. Laboratory test results indicate natural moisture contents ranged from 18.9% to 22.9%, a liquid limit of 37, a plasticity index of 18 with 92.8% fines.

### ***Bloody Pond Tour Stop***

The AC thickness encountered in Borings BP-1 and BP-2 varied from 60 to 90 mm with no aggregate base.

Beneath the pavement in Boring BP-1, reddish brown silt with trace clay and sand (A-4) was encountered to the termination depth of 2.1 m. Laboratory test results indicate a natural moisture content of 20.4%, a liquid limit of 31, non-plastic plasticity index and 88.4% fines. SPT resistances ranged from 7 to 22 blows per 300 mm indicating stiff to very stiff consistencies.

Beneath the pavement in Boring BP-2, brown sandy clay with trace silt (A-6) was encountered to the termination depth of the boring. Laboratory test results indicate a natural moisture content of 15.7%, a liquid limit of 32, a plasticity index of 13 and 69.1% fines. SPT resistances ranged from 9 to 18 blows per 300 mm indicating stiff to very stiff consistencies.

### ***Groundwater***

No groundwater was encountered during or after completion of drilling in any of the borings. Fluctuations in the groundwater level due to seasonal and climatic effects should be expected.

## **ANALYSIS AND CONCLUSIONS**

### **Pavements**

Flexible pavement design analyses were conducted for overlay, reconstruction and new construction areas using the 1997 AASHTO Pavement Design, DARWin(tm) Pavement Design

System (version 3.01). DARWin was used to determine the future structural number (SN) for each pavement section. Flexible pavement design analyses were conducted for a 20-year design period. The design analyses to determine the 80-kN equivalent single axle loads (ESAL's) were performed using the Rigorous ESAL Calculation in DARWin and were based upon traffic count and vehicle classification data obtained from the Design Scoping Report. Initial Average Daily Traffic (ADT) values were estimated from the reported 1995 ADT values by figuring a 2 percent annual growth from 1995. The effective roadbed soil resilient modulus was determined from the CBR tests that were correlated to the resilient modulus ( $M_R$ ). Resilient moduli used for the analysis were 62055 and 72398 kPa, which correspond to CBR's of 6 and 7, respectively. Other parameters specified in the analyses include a reliability of 85 percent, and overall standard deviation of 0.49, an initial serviceability index of 4.2, and a terminal serviceability index of 2.2. The results of the pavement design analysis are presented in Appendix G.

For constructibility reasons, analyses of new pavement sections and reconstruction areas considered a minimum section consisting of 40 mm of SACP surface course (12.5 mm NMSA); 60mm of SACP base course (19 mm NMSA) and 200mm of aggregate base (grading C or D). Also, for constructibility reasons, analyses of overlay sections considered a minimum course of 40 mm SACP (12.5 mm NMSA).

#### Structural plate-arch pipe Foundations

The foundations for the proposed structural plate pipe-arch on Reconnoitering road were analyzed. Bearing capacity analysis was performed for spread footings based on assumed footing widths of 1.5, 2.0 and 2.5 m and a length of 6.5 m. Allowable bearing capacity calculations were performed using methods from AASHTO Standards for design of Highway Bridges (AASHTO, 1996) and Foundation Analysis and Design, Bowles, 1996. Calculations were performed assuming a 0.76 m overburden below the stream bed. Results for no overburden are also presented in the recommendations section. The results of the spread footings analysis are presented in Tables 3 and 4. Bearing capacity calculations are presented in Appendix D. Calculated total settlements for the spread footings at the allowable loads are expected to be 15, 20 and 25 mm, respectively. No scour data was available at the time of writing this report. Once scour data is provided, these foundation recommendations will be verified or revised as required.

**TABLE 3 - ALLOWABLE BEARING CAPACITY RESULTS  
ASSUMING 0.76 m OVERBURDEN**

<b>Footing Dimensions (m)</b>	<b>Ultimate Bearing Capacity (KPa)</b>	<b>Factor of Safety</b>	<b>Allowable Bearing Capacity (KPa)</b>
6.5 x 1.5	426	3	142
6.5 x 2.0	495	3	165
6.5 x 2.5	537	3	179

**TABLE 4 - ALLOWABLE BEARING CAPACITY RESULTS  
ASSUMING NO OVERBURDEN**

<b>Footing Dimensions (m)</b>	<b>Ultimate Bearing Capacity (KPa)</b>	<b>Factor of Safety</b>	<b>Allowable Bearing Capacity (KPa)</b>
6.5 x 1.5	183	3	61
6.5 x 2.0	249	3	83
6.5 x 2.5	300	3	100

## **RECOMMENDATIONS**

### **Pavements**

The following pavement recommendations are based on the pavement condition survey performed during August 1999, subsurface exploration and laboratory test results and analysis.

**General** - The recommended general procedure for rehabilitation of the roadways, turnarounds and parking areas consists of full-depth spot reconstruction followed by an SACP overlay. It is recommended to place 0.75 m wide strips of paving geogird over existing low to high severity fatigue, longitudinal and transverse cracks prior to placing the overlay.

It is recommended the pavement reconstruction and new construction areas to consist of 40 mm of SACP surface course, 60 mm of SACP base course and 200 mm aggregate base (grading C or D). The recommended SACP surface and base courses mix designs for the project are 12.5 mm nominal maximum size aggregate (NMSA),  $<0.3 \times 10^6$  EASL's and 19 mm NMSA,  $<0.3 \times 10^6$  EASL's; respectively.

Recommendations for each specific site are presented below.

#### ***Brown's Landing Road (NPS Route 502)***

It is recommended to overlay Brown's Landing road using 50 mm SACP overlay (12.5 mm NMSA). It is recommended to use the above described pavement section for widening of the road.

#### ***Pittsburg Landing Road I (NPS Route 13)***

It is recommended to overlay Pittsburg Landing I road using 50 mm SACP overlay. It is recommend to construct the realigned section of Pittsburg Landing road I using 40 mm of SACP surface course, 60 mm of SACP base course and 200 mm aggregate base (grading C or D).

### ***Visitor Center and Cemetery Parking Areas***

It is recommended to overlay the Visitor Center and Parking area using 50 mm SACP overlay. Pavement reconstruction areas within the parking lot are recommended to consist of 40 mm of SACP surface course, 60 mm of SACP base course and 200 mm aggregate base (grading C or D).

### ***Pittsburg Landing Road II***

It is recommended to overlay Pittsburg Landing II road using 50 mm SACP overlay.

### ***Reconnoitering Road (NPS Route 500)***

It is recommended to overlay Reconnoitering road using 50 mm SACP overlay.

### ***Corinth-Pittsburg Landing Road (NPS Route 12)***

Based on the pavement condition survey and scoping report, RPCC slab replacement and joint repair are the recommended rehabilitation procedures. Approximately 33% of the RPCC slabs will require replacement. It is recommended to clean and seal all longitudinal and transverse joints. A list of the slab numbers, type of defects and recommended replacement or joint repair is presented in Table 1 in Appendix F.

### ***Entrance Road***

Based on the pavement condition survey, it is recommended to place an SACP wedge and level course prior to placement of the AC overlay for the existing portion of the Entrance road that is to remain in use. The overlay is recommended to consist of 65 mm SACP overlay (12.5 mm NMSA).

Based on the information provided by Project Development, the new Entrance road will be realigned. It is recommended to construct the new roadway alignment using the minimum recommended pavement section described previously.

### ***McClernand Road***

It is recommended to overlay McClernand road using 65 mm SACP overlay (12.5 mm NMSA).

### ***Eastern Corinth road I (NPS Route 14)***

It is recommended to overlay Eastern Corinth road I using 50 mm SACP overlay (12.5 mm NMSA). Prior to placement of the SACP overlay, perform spot reconstruction or place a paving geogrid at the locations shown in Table 5.

**TABLE 5 - SPOT RECONSTRUCTION AND PAVING GEOGRID  
RECOMMENDATIONS**

<b>Approximate Stations</b>	<b>Lane Width</b>	<b>Reconstruction Type</b>
10+000 to 10+150	Both lanes, full	Full-depth spot reconstruction
10+175 to 10+290	Both lanes, full	Full-depth spot reconstruction, part of the realignment
10+650 to 10+670	SB lane, full	Full-depth spot reconstruction
10+685 to 10+710	Both lanes, full	Paving geogrid
10+820 to 10+850	Both lanes, full	Paving geogrid
11+082	Both lanes, full	Paving geogrid
11+088 to 11+095	Both lanes, full	Full-depth spot reconstruction

***Peabody Road (NPS Route 501)***

It is recommended to overlay Peabody road using 50 mm SACP overlay (12.5 mm NMSA).

***Hamburg-Savannah Road (NPS Route 11)***

It is recommended to overlay Hamburg-Savannah road using 70 mm overlay (12.5 mm NMSA). Prior to placement of the overlay full-depth spot reconstruction should be performed in the area between stations 10+780 and 10+900. It is recommended to place paving geogrid on the transverse cracks between stations 10+600 and 10+650.

***New One-way Loop Around Tent Hospital Site***

It is recommended to construct the new one-way loop using 40 mm SACP surface course, 60 mm SACP base course and 200 mm aggregate base (grading C or D).

***Johnston Memorial***

Based on the pavement condition survey, it is recommended to perform full-depth spot reconstruction in the area around the memorial at the locations shown on the drawing in Appendix B. Full-depth spot reconstruction is recommended to consist of 40 mm SACP surface course, 60 mm SACP base course and 200 mm aggregate base course (grading C or D).

***Peach Orchard Parking***

For widening of Peach Orchard Parking area, it is recommended to use the minimum recommended pavement section consisting of 40 mm SACP surface course, 60 mm SACP

base course and 200 mm aggregate base course.

### ***Bloody Pond Tour Stop***

It is recommended to use 40 mm SACP surface course, 60 mm SACP base course and 200 mm aggregate base course for reconstruction of the roadway and 2 turnouts at Bloody Pond Tour Stop.

### **Foundations - Structural plate-arch pipe**

It is recommended to support the new structural plate pipe-arch on Reconnoitering road on spread footings founded on competent soils. Allowable bearing capacities for footing widths of 1.5, 2.0 and 2.5 m are 142, 165 and 179 KPa, respectively, assuming 0.76 m of overburden. Allowable bearing capacities were also calculated assuming no overburden for footing widths of 1.5, 2.0 and 2.5 m as 61, 83 and 100 KPa, respectively. Total settlements are estimated at 15, 20 and 25 mm based on allowable bearing pressures of 142, 165 and 179 KPa, respectively. Differential settlements are expected to be approximately half of the total settlement values.

### ***Culverts***


Metal pipe culvert service life can be estimated based on a pH of 4.5 and a minimum electrical resistivity of 10,000 ohm-cm.


### ***Construction Considerations***

The majority of the subgrade soils at the project site are moderate to high plasticity clay. Some subexcavation and replacement with unclassified borrow (or better) is anticipated in spot reconstruction and new construction areas. It is recommended to include a quantity of 250 cubic meter of subexcavation and replacement in the contract.

### **DISCLAIMER/LIMITATIONS CLAUSE**

The subsurface explorations and tests described in the section on Procedures and Results have been conducted in accordance with standard practices and procedures (except as specifically noted). The results of these explorations and tests represent conditions at the specific locations indicated. Subsurface conditions between these locations may vary. The Analysis and Conclusions sections and the Recommendations section in this report include interpretations and recommendations developed by the Government in the process of preparing the design. These interpretations are not intended as a substitute for the personal investigation, independent interpretation, and judgment of the Contractor.



  
Prepared by:  
Khalid T. Mohamed  
Geotechnical and Pavement Engineer

  
Reviewed by:  
William Bassett, P.E.  
Supervisory Geotechnical Engineer



## **APPENDIX A - Figures**

REG	STATE	PROJECT	SHEET NO.	TOTAL SHEETS
SE	TENN	PRA-SHIL 502(I), ETC.		



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

LOCATION MAP

FIGURE 1

GEOTECHNICAL REPORT 24-99









REG	STATE	PROJECT	SHEET NO.	TOTAL SHEETS
SE	TNN	PRA-SHIL 502(I), ETC.		

## SOILS MAP



- 6 WOLFTEVER-BEASON-EGAM ASSOCIATION  
NEARLY LEVEL SOILS ON LOW STREAM TERRACES AND FLOOD PLAINS OF THE TENNESSEE RIVER
- 3 PADEN-PICKWICK-WAYNESBORO ASSOCIATION  
MODERATELY WELL DRAINED SOILS AND WELL DRAINED SOILS ON HIGH TERRACES

## GEOLOGIC MAP



- High-level alluvial deposits  
IRON-STAINED GRAVEL, SAND, SILT, AND CLAY; VARIABLE IN THICKNESS BUT GENERALLY LESS THAN 80 FEET THICK.
- Alluvial deposits  
SAND, SILT, CLAY, AND GRAVEL; GENERALLY LESS THAN 20 FEET THICK.
- Eutaw formation  
GRAYISH-GREEN SAND, FINE-GRAINED, GLAUCONITIC, MICACEOUS; INTERBEDDED WITH GRAY LAMINATED CLAYS WHICH COMMONLY CONTAIN CARBONIZED OR SILICIFIED WOOD. THICKNESS 0 TO 180 FEET; THINS NORTHWARD.
- Coffee sand  
LOOSE, FINE-GRAINED SAND, LIGHT-GRAY, SPARSELY GLAUCONITIC, LOCALLY INTERBEDDED WITH LAMINATED LIGNITIC CLAY. THICKNESS 25 TO 200 FEET; THINS NORTHWARD.

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

GEOLOGY MAPS



FIGURE 3

GEOTECHNICAL REPORT 24-99



**APPENDIX B - Boring Location Plan**

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000	SE	TN	PRA-SHIL 502(1), ETC.	
00000				





U.S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION  
 STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK  
 BROWN'S LANDING ROAD  
 1+000 to 1+350

SCALE IN FEET  
 0 10 20

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000	SE	TN	PRA-SHIL 502(1), ETC.	
00000				





U.S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL HIGHWAY DIVISION  
 STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK  
 PITTSBURG LANDING ROAD  
 20+000 to 20+700

0 10 20  
 SCALE IN METERS

Sheet 1 of 3

NPS NO.	STATE	PROJECT	SHEET NO.
000	SE	PRA-SHIL 502(U), ETC.	
00000			



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL HIGHWAY DIVISION  
STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK

**BORING LOCATIONS PLAN**  
**PITTSBURG LANDING ROAD**  
**20+700 to 21+400**


Curve PITT13-6  
Δ = 2019 56.09° (LT)  
R = 150,000 m  
T = 26,898 m  
L = 53,230 m

SCALE IN METERS  
0 10 20



Sheet 2 of 3



NPS NO.	REG	STATE	PROJECT	SHEET NO.
000000	SE	TN	PRA-SHIL 502(II), ETC.	



NPS NO.	REG	STATE	PROJECT	SHEET NO.
0000	SE	TN	PRA-SHIL 50201, ETC.	
00000				



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA



SHILOH NATIONAL MILITARY PARK

**BORING LOCATIONS PLAN**  
CORINTH-PITTSBURG LANDING ROAD  
31+400 to 32+100

0 10 20  
METERS

Sheet 3 of 8

NPS NO.	REC	STATE	PROJECT	SHEET NO.
000000	SE	TN	PRA-SHIL 502(U), ETC.	





U.S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION  
 STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK  
**BORING LOCATIONS PLAN**  
 CORINTH-PITTSBURG LANDING ROAD  
 32+100 to 32+800

SCALE IN FEET  
 0 10 20



Sheet 4 of 8

NP'S NO.	REG	STATE	PROJECT	SHEET NO.
000 00000	SE	TN	PRA-SHIL 50210, ETC.	





NPS NO.	REG	STATE	PROJECT	SHEET NO.
000000	SE	TN	PRA-SHIL 50210, ETC.	




U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK  
**BORING LOCATIONS PLAN**  
CORINTH-PITTSBURG LANDING ROAD  
34+200 to 34+900

SCALE IN FEET

Sheet 7 of 8

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000	SE	TN	PRA-SHIL 502(II), ETC.	
00000				



U.S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION  
 STERLING, VIRGINIA


SHILOH NATIONAL MILITARY PARK

**BORING LOCATIONS PLAN**  
 CORINTH-PITTSBURG LANDING ROAD  
 34+900 to 35+020

0 10 20  
 SCALE IN FEET

Sheet 8 of 8



NPS NO.	REG.	STATE	PROJECT	SHEET NO.
000000	SE	TN	PRA-SHIL 50200, ETC.	



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA  
SHILOH NATIONAL MILITARY PARK  
**BORING LOCATIONS PLAN**  
McCLERNAND ROAD  
40+000 to 40+403



NP'S NO.	REC	STATE	PROJECT	SHEET NO.
000	SE	TN	PRA-SHIL 502(1), ETC.	
00000				



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK

## BORING LOCATION PLAN



SHERMAN ROAD  
50+000 to 50+480

SCALE IN METERS  
0 10 20

NPS NO.	REG	STATE	PROJECT	SHEET NO.
00000000	SE	TN	PRA-SHL 502(U), ETC.	

Begin realignment  
Eastern Corinth Road 60+025.0

End realignment/Begin 50 mm HACF.  
class B grading D overlay  
Eastern Corinth Road 60+180.0




U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA


SHILOH NATIONAL MILITARY PARK

# BORING LOCATION PLAN EASTERN CORINTH ROAD 60+000 to 60+700

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000000	SE	TN	PRA-SHIL 502(II), ETC.	



End 50 mm HACP, class B, grading D overlay  
Eastern Corinth Road 6I+014.7



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, NC, VIRGINIA

SHILOH NATIONAL MILITARY PARK  
**BORING LOCATION PLAN**  
EASTERN CORINTH ROAD  
60+700 to 61+014

0 10 20  
METERS  
Sheet 2 of 2

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000	SE	TN	PRA-SHIL 502(II), ETC.	
00000				

Begin 50 mm HACP, class B, grading D overlay  
Peabody Road 70+000.0

POT 70+000.000  
Tour Stop #10

Sta. 70+025 Construct  
2-Bus Parking Area

Construction C/L

POT 70+007.5 Peabody Road  
POT 11+238.3 Reconnaitering Road

RECONNAITERING ROAD

11+200

PEABODY ROAD

RS-1

70+250

70+200

70+150

70+100

70+050

70+250

70+300

70+350

70+400

70+450

70+550

760 mm x 14 m RCP &  
stone headwalls to remain.

Construction C/L

PEABODY ROAD

RS-2

Existing 405 mm x 10.8 m RCP  
& 2 stone headwalls to remain.

Construct 2 bus turnout

POC 70+597.0 Peabody Road  
POT 60+182.9 Eastern Corinth Road

AT 60+155.306

POT 60+163.594

Convert existing road  
to a paved trail

End 50 mm HACP, class B, grading D overlay  
Peabody Road 70+597.0

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK



BORING LOCATIONS PLAN

PEABODY ROAD  
70+000 to 70+596

SCALE IN METERS  
0 10 20



NPS NO.	REG	STATE	PROJECT	SHEET NO.
000 00000	SE	TN	PRA-SHIL 502(II), ETC.	



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA


SHILOH NATIONAL MILITARY PARK

**BORING LOCATION PLAN**  
HAMBURG-SAVANNAH ROAD  
81+250 to 81+950

0 10 20  
SCALE IN METERS

Sheet 3 of 4

NPS NO.	REG	STATE	PROJECT	SHEET NO.
000 00000	SE	TN	PRA-SHL 502(1), ETC.	



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION  
STERLING, VIRGINIA

SHILOH NATIONAL MILITARY PARK

# BORING LOCATIONS PLAN

TENT HOSPITAL SITE  
90+000 to 90+357

SCALE: 1" = 100'

Curve T-1	Curve T-2	Curve T-3
$\Delta = 92^\circ 10' 31.6''$ (LT)	$\Delta = 217^\circ 39' 19.9''$ (LT)	$\Delta = 37^\circ 53' 27.33''$ (RT)
$R = 40,000$ m	$R = 15,000$ m	$R = 40,000$ m
$T = 41,548$ m	$T = 43,992$ m	$T = 13,731$ m
$L = 64,351$ m	$L = 56,982$ m	$L = 26,455$ m

## **APPENDIX C - Boring Logs**



## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 1½" I.D., 2" O.D., except where noted

ST: Shelby Tube - 2" O.D., except where noted

PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible even after several days, and additional information on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

#### Component     Distinguishing Features

Boulders     Larger than 3"

#### Gravel

Coarse	1" to 3"
Medium	¾" to 1"
Fine	No. 10 to ¾"

Sand     The finest sand grains are just visible to the naked eye, while the largest would pass a No. 10 sieve (pinhead size).

Silt     1. Lumps are easily crumbled when air-dried.  
2. Feels gritty between the teeth.  
3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.

Clay     1. Lumps are comparatively hard when air-dried.  
2. Threads (⅛" in diameter) of considerable length will support their own weight when held by one end.  
3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

#### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term -     "AND" : 40% to 50% of the minor grain size  
                                     "SOME" : 10% to 40%  
                                     "TRACE": 10% or less
5. Minor Grain Size(s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

Project Name: <b>PRASHIL 502(1)</b>										Boring No. <b>R-1</b>		Date: <b>8-6-96</b>		Sheet <b>1</b> of <b>1</b>	
Boring Location: <b>RECONNOITERING ROAD</b>										Type of Boring: <b>SS</b>			Drilling Mud Type: <b>N/A</b>		
										Casing Used: <b>SOLID</b>		Size: <b>4 1/2</b>			
Water Level										Boring Began: <b>8-6-96</b>			Completed: <b>8-6-96</b>		
Time										Ground Elevation:			Weather: <b>CLEAR</b>		
Date										Inspector: <b>THORNTON</b>			Operator: <b>KINGSLEY HUGHES</b>		
										Hammer Weight <b>63.5 +/- 1kg</b>					
										DESCRIPTION					
										<b>0.08 AC</b> <b>0.07 AGG. BASE</b> <b>Very stiff, reddish brown, CLAY, some silt, trace fine sand (moist)</b>					
<b>J-1 SS</b> <b>0.31</b> <b>0.41</b> <b>4.5</b> <b>8</b> <b>10</b> <b>14</b> <b>18</b>										<b>0.0</b> <b>0.31</b>   <b>0.91</b>					
<b>J-2 SS</b> <b>0.91</b> <b>1.52</b> <b>0.61</b> <b>4.5</b> <b>8</b> <b>12</b> <b>16</b> <b>20</b>										       <b>1.52</b>					
										<b>BPT @ 1.52 m</b>					

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1) (2) (3) (4) (5) (4) (5) (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
↑ ↑  
(10% - 40%) (1% - 10%)

NIA

Weather: CLEAR

Operator: HUGHES, KINGSLLEY

Hammer Weight 63.5 +/- 1kg

[illegible]

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

[illegible]

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
  ↑                    ↑  
   (10% - 40%)       (1% - 10%)

# BORING LOG

[illegible]



## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"            :      40% to 50% of the minor grain size  
                             "SOME"           :      10% to 40%  
                             "TRACE"          :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)								Boring No.	VC-1	Date:	8-6-96	Sheet	1 of 1				
Boring Locations VISITOR CENTER & CEMETERY PARKING AREAS								Type of Boring:	SS		Drilling Mud Type:						
								Casing Used:	SOLID	Size:	4 1/2	N/A					
Water Level								Boring Begon:		8-6-96		Completed:		8-6-96			
Time								Ground Elevation:		Weather: CLEAR							
Date								Inspector:		THORTON		Operator:				HUGHES, KINGSLLEY	
								Hammer Weight		63.5 +/- 1kg							
								DESCRIPTION									
J-1	SS	0.31	0.91	0.56	4.0	2	6	6	8	0.31	0.91	AC AGG. BASE			Stiff to very stiff, brown, CLAY, little to some sand (moist-)		
J-2	SS	0.91	1.52	0.60	4.5	3	8	11	15	0.91	1.52	BENT @ 1.52 m					

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

(1)           (2)         (3)      (4)      (5)       (4)      (5)   (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  

↑  
(10% - 40%)

↑  
(1% - 10%)

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)				Boring No. VC-2	Date: 8-6-96	Sheet 1 of 1
Boring Locations: VISITOR CENTER & CEMETERY PARKING AREAS				Type of Boring: SS		Drilling Mud Type:  N/A
				Casing Used: SOLID	Size: 4 1/2	
Water Level				Boring Began: 8-6-96	Completed: 8-6-96	
Time				Ground Elevation:		Weather: CLEAR
Date				Inspector: THORNTON		Operator: HUGHES, KINGSLEY

[illegible]

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

[illegible]




U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)				Boring No. VC-4		Date: 8-6-96		Sheet 1 of 1	
Boring Location: VISITOR CENTER & CEMETERY PARKING AREAS				Type of Boring: SS			Drilling Mud Type:  N/A		
				Casing Used: SOLID		Size: 4 1/2			
Water Level				Boring Began: 8-6-96		Completed: 8-6-96			
Time				Ground Elevations:			Weather: CLEAR		
Date				Inspector: THORNTON			Operator: HUGHES, KINGSLEY		

[illegible]

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

[illegible]



## BORING LOG

 U.S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: <b>PRA SHIL 502 (1)</b>				Boring No. <b>VC-6</b>	Date: <b>8-9-96</b>	Sheet <b>1</b> of <b>1</b>
Boring Location: <b>VISITOR CENTER &amp; CEMETERY PARKING AREAS</b>				Type of Boring: <b>SS</b>		Drilling Mud Type: <b>N/A</b>
				Casing Used:	Size: <b>4 1/2</b>	
Water Level				Boring Began: <b>8-9-96</b>		Completed: <b>8-9-96</b>
Time				Ground Elevation:		Weather: <b>CLEAR</b>
Date				Inspector: <b>THORTON</b>		Operator: <b>HUGHES, KINGSLY</b>

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

AC

AGG. BASE

 Stiff to hard, red, CLAY, some  
 sand, trace silt (moist-)

BHT@ 2.13 m

[illegible]

Water Level			Boring Began: 8-1-96	Completed: 8-1-96
Time			Ground Elevations:	Weather: CLEAR
Date			Inspector: THORNTON	Operator: KINGLEY HUGHES

$P \approx 0.012$

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(C)				Boring No. PLI-3	Date: 8-9-96	Sheet 1 of 1
Boring Location: PITTSBURGH LANDING ROAD (E)				Type of Boring:		Drilling Mud Type: NIA
				Casing Used: SOLID	Size: 3 1/4"	
Water Level				Boring Began: 8-9-96	Completed: 8-9-96	
Time				Ground Elevation:		Weather: CLEAR
Date				Inspector: THORNTON	Operator: KINGSLEY / HUGHES	

[illegible]

Project Name: PRA SHIL 502(1)

Boring No. PLI-4

Date: 8-1-96

Sheet 1 of 1

### Boring Locations:

Type of Boring:

Drilling Mud Type:

PITTSBURGH LANDING ROAD (I)

Casing Used: SOLID

Size: A 1/2"

NIA

Water Level

Boring Began: 8-1-96

Completed: 8-1-96

Time

Ground Elevations:

Weather: CLEAR

Date \_\_\_\_\_

Inspector: THORNTON

Operator: KINGSLEY | HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.09

AC

AGG. BASE

Soft to medium stiff, reddish brown, CLAY, trace sand, trace silt, (moist-)

B4T @ 1.62 m



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)				Boring No. PLT-5	Date: 8-1-96	Sheet 1 of 1
Boring Location: PITTSBURGH LANDING ROAD (E)				Type of Boring:		Drilling Mud Type: NIA
				Casing Used: SOLID	Size: 4 1/2"	
Water Level				Boring Began: 8-1-96	Completed: 8-1-96	
Time				Ground Elevations:		Weather: CLEAR
Date				Inspector: THORNTON	Operator: KINGSLEY / HUGHES	

[illegible]

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

[illegible]

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Sheet 1 of 1

Drilling Mud Type:

Size: 4 1/2"

NIA

Completed: 8-1-96


Weather: CLEAR

Operator: KINGSLEY | HUGHES

DESCRIPTION

Bottom of Pavement Core  
@ 0.19 m

## BORING LOG

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: <b>PRA SWIL 502(1)</b>										Boring No. <b>PLI-8</b>		Date: <b>8-1-96</b>		Sheet <b>1</b> of <b>1</b>	
Boring Location: <b>PITTSBURG LANDING ROAD (E)</b>										Type of Boring:				Drilling Mud Type:	
										Casing Used: <b>SOLID</b>		Size: <b>4 1/2"</b>		NIA	
Water Level								Boring Began: <b>8-1-96</b>				Completed: <b>8-1-96</b>			
Time								Ground Elevation:				Weather: <b>CLEAR</b>			
Date								Inspector: <b>THORNTON</b>				Operator: <b>KINGSLEY / HUGHES</b>			
										Hammer Weight <b>63.5 +/- 1kg</b>					
										DESCRIPTION					
										<b>0.09 AC</b> <b>0.07 AGG. BASE</b>					
J-1 SS										Bottom of pavement core at 0.16 m					
J-2 SS															

Drilling Mud Type:

N/A

Completed: 8-8-96

Weather: CLEAR

Operator: KINGSLLEY, HUGHES

DESCRIPTION

Stiff to very stiff, brown, clay,  
trace sand, trace silt, (moist)

Bottom of hole @ 1.93 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1) (2) (3) (4) (5) (4) (5) (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
↓ ↓  
(10% - 40%) (1% - 10%)

[illegible]

Soft to very stiff, reddish brown,  
CLAY, trace sand, trace  
silt (moist)

BH @ 1.93

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>


### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		





# BORING LOG

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑ (10% - 40%)		↑ (1% - 10%)		



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: <b>PRA SHIL 502(1)</b>					Boring No. <b>PLI-12</b>		Date: <b>8-8-96</b>		Sheet <b>1 of 1</b>		
Boring Location: <b>PITTSBURG LANDING RD (E)</b>					Type of Boring: <b>SS</b>			Drilling Mud Type: <b>NIA</b>			
					Casing Used: <b>SOLID</b>		Size: <b>4 1/2</b>				
Water Level					Boring Begon: <b>8-8-96</b>			Completed: <b>8-8-96</b>			
Time					Ground Elevation:			Weather: <b>CLEAR</b>			
Date					Inspector: <b>THORNTON</b>			Operator: <b>KINGSLEY/HUGHES</b>			
					Hammer Weight <b>63.5 +/- 1kg</b>						
					<b>DESCRIPTION</b>						
					<b>0-11 AC</b> <b>0.07m AGG BASE</b> <b>Bottom of Coring depth</b> <b>at 0.18m</b>						

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

# BORING LOG

Project Name: PRA SHIL 502(1)

Boring No. PL II - 1 Date: 8-1-96 Sheet 1 of 1

Boring Location:

Type of Borings: SS

Drilling Mud Type:

PITTSBURGH LANDING RD (II)

Casing Used: SOLID	Size: 4 1/2"
--------------------	--------------

NIA

### Water Level

Boring Began: 8-1-96

Completed: 8-1-96

Time

### Ground Elevations:

Weather: CLEAR

Date \_\_\_\_\_

Inspector: THORNTON      Operator: KINGSLEY, HUGHES

Hammer Weight 63.5 +/- 1kg

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"            :      40% to 50% of the minor grain size  
                             "SOME"          :      10% to 40%  
                             "TRACE"        :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			(10% - 40%)		(1% - 10%)		



Boring No. <u>PLI-3</u>	Date: <u>8-12-96</u>	Sheet 1 of 1
Type of Boring: <u>SS</u>		Drilling Mud Type:
Casing Used: <u>4 1/2"</u>	Size: <u>6 3/4"</u>	<u>N/A</u>

Boring Began: 3-12-96	Completed: 3-12-96
Ground Elevations:	Weather: CLEAR
Inspector: THORNTON	Operator: KINGSLEY, HUGHES

Hammer Weight 63.5 +/- 1kg

late

DESCRIPTION

AC  
AGG BASE

very loose to loose, brown, silty  
SAND, trace chert- (moist)

(FILL)

brown, silty sand,  
(moist)

Medium stiff, red, CLAY, some  
silt, trace f. sand (moist)

BHT @ 3.35 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↑		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Boring No. CP-3	Date: 8-13-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: CORE	Size: 4 1/2	N/A
Boring Begon: 8-13-96	Completed: 8-13-96	
Ground Elevation:	Weather: CLEAR	
Inspector: THORNTON	Operator: KINGLEY/HUGHES	
Hammer Weight 63.5 +/- 1kg		

[illegible]

DESCRIPTION

0.16 m R.P.C.C

Stiff to very stiff, brown.  
CLAY, some silt, trace f.  
Sand (moist)

BHTO 1.37 m

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

### Order of Description

- For example:

h:\usr\soils\forms\abldes.wpd

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Sheet \ of \

58

Size: 4 1/2"

21A

Completed: 8-13-96

Weather: CLEAR

Operator: KINGSLY/HUGHES

[illegible]

DESCRIPTION

0.13 m RPCC.

Medium stiff to very stiff, brown,  
CLAY, little silt. trace sand  
(moist-)

BHT @ 1.35 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		



Boring No. CP-4 Date: 8-13-96 Sheet 1 of 1

Type of Boring:	SS	Drilling Mud Type:
-----------------	----	--------------------

Casing Used: <i>core</i>	Size: <i>4 1/2</i>	<i>21A</i>
--------------------------	--------------------	------------

Water Level	Boring Begon: 8-13-96	Completed: 8-13-96
-------------	-----------------------	--------------------

				Ground Elevation:	Ground Elevation:
--	--	--	--	-------------------	-------------------

at			Inspector: THORNTON	Operator: KINGSLEY/HUGHES
----	--	--	---------------------	---------------------------

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.13 m RPCC

Medium stiff, to very stiff,  
brown, CLAY, some silt,  
trace f. sand (moist)

BHT @ 1.35

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

(1)            (2)            (3)            (4)            (5)            (4)            (5)            (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  

↑                                  ↑  
(10% - 40%)                 (1% - 10%)

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

~~But~~ 1.34 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		



# BORING LOG

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: **PRA SHIL 502C1)**

Boring No. **CP-7**

Date: **8-14-96**

Sheet **1** of **1**

Boring Location:

**CORINTH - PITTSBURGH RD**

Type of Boring: **SS**

Drilling Mud Type:

Casing Used: **COLE**

Size: **4 1/2"**

**N/A**

Water Level

Boring Began: **8-14-96**

Completed: **8-14-96**

Time

Ground Elevation:

Weather: **CLEAR**

Date

Inspector: **THORNTON**

Operator: **KINGSLEY/HUGHES**

Hammer Weight **63.5 +/- 1kg**

Sample Number	Sample Type	Depth From To (Meters)	Total Length of Recovered Sample	Pocket Penetrometer Kg/cm2	Torvane Kg/cm2	No. of Blows on Sampler for 158mm Increments	Depth (Meters)	Elevation (Meters)
							0.19	
1	SS	0.19 0.80	0.40	3.0		3 1		
						3	0.80	
2	SS	0.80 1.41	0.55	2.0		1 1		
						1	1.41	
3	SS	1.41 2.02	0.40	—		1 1		
						1	2.02	
4	SS	2.02 2.63	0.50	—		won't		
						↓	2.63	
5	SS	2.63 3.24	0.45	—		1 2		
						3	3.24	

## DESCRIPTION

0.07m — AC  
0.12m RPCC

Very soft to stiff, gray, SILT, some clay, some f.m. Sand (moist to wet)

Very soft to medium stiff, gray, some f.m. Sand, some clay (wet)

BATT@ 3.24m

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Boat (a) 3.23 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
 ST: Shelby Tube - 50mm O.D., except where noted  
 PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"            :      40% to 50% of the minor grain size  
                              "SOME"          :      10% to 40%  
                              "TRACE"        :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

# BORING LOG

Project Name: PRA SHIL 502C1

Boring No. CP-9

Date: 8-14-96

Sheet \ of \

### Working Location:

Type of Boring:

58

Drilling Mud Type:

CORINTH PITTSBURGH RD

Casing Used: Cole

Size: 4 1/2

21A

Star Level

Boring Began: 8-14-96

Completed: 8-14-96

ime

### Ground Elevations:

Weather: CLEAR

etc

Inspector: Thornton

Operator: KINGSLY/HUGHES

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

[illegible]

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
 ST: Shelby Tube - 50mm O.D., except where noted  
 PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"        :        40% to 50% of the minor grain size  
                         "SOME"        :        10% to 40%  
                         "TRACE"     :        10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Bolt @ 1.35 m

## Drilling and Sampling Symbols

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

<u>Component</u>	<u>Distinguishing Features</u>
------------------	--------------------------------

### Order of Description

- For example:

h:\usr\soils\forms\Abldes.wpd

Sheet 1 of 1

Drilling Mud Type:

NIA

Completed: 8-13-96

Weather: CLEAR

Operator: KINGSLEY HUGHES

[illegible]

DESCRIPTION

0.13 m RDC

very loose to loose, brown,  
clayey, f-m SAND, some  
silt (moist)

BHTO 1-35m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Boring No. CP-12 Date: 8-6-96 Sheet 1 of 1

Type of Boring:	SS	Drilling Mud Type:
Casing Used: CORE	Size: 4 1/2	

Boring Began: 8-6-96	Completed: 8-6-96
----------------------	-------------------

Ground Elevations:                      Weathers: CLEAR

Inspector: THORNTON      Operator: KINGSLEY/HUGHES

Sample Number	Sample Type	Depth From --To (Meters)	Total Length of Recovered Sample	Pocket Panelometer Kg/cm2	Torvane Kg/cm2	No. of Blows on Sampler for 150mm Increments	Depth (Meters)	Elevation (Meters)
---------------	-------------	--------------------------	----------------------------------	---------------------------	----------------	--	----------------	--------------------

					1	
					1	
1	SS	0.31		1.55	2	
		0.61			3	0.61
					5	
					9.	
-2	SS	0.61		4.5	12.	
		1.22			18	1.22
					4	
					9.	
-3	SS	1.22		3.5	12.	
		1.93			16	1.93

[illegible]

BCHT@ 1.93 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"       :       10% to 40%  
                      "TRACE"      :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

BHT (2) 1.52

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
  ↑                    ↑  
   (10% - 40%)       (1% - 10%)



## BORING LOG

 U. S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)

Boring No. MS-2 Date: 8-6-96 Sheet 1 of 1

Boring Location: MCCLERNAND ROAD

Type of Boring: SS Drilling Mud Type:

Casing Used: SLD Size: 4 1/2" NIA

Water Level

Boring Began: 8-6-96 Completed: 8-6-96

Time

Ground Elevation: Weather: CLEAR

Date

Inspector: WORTON Operator: KINGSLEY/HUGHES

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

0-08 AC

 very soft to medium stiff,  
 brown, CLAY, some silt,  
 trace f. sand (moist).

BHT @ 1.52 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

Boring No. MS-3	Date: 8-6-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: SOLID	Size: 4 1/2	N/A

Boring Begon: 8-6-96	Completed: 8-6-96
Ground Elevations:	Weather: CLEAR
Inspector: THORNTON	Operator: KINGSLLEY HUGHES

Water Level										Boring Begins 8-6-96										Completed: 8-6-96									
Time										Ground Elevations:										Weather: CLEAR									
Date										Inspector: THORNTON										Operator: KINGLEY/HUGHES									
										Hammer Weight 63.5 +/- 1kg																			

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



Boring No. MS-4	Date: 8-6-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: Solid	Size: 4 1/2"	N/A

Boring Begins: 8-6-96	Completed: 8-6-96
Ground Elevations:	Weather:
Inspector: THORNTON	Operator: KINGSLEY / HUGHES
Hammer Weight 63.5 +/- 1kg	

10 to

DESCRIPTION

soft to very stiff, brown,  
CLAY, some silt, trace f-  
sand (moist)

BHT @ 1.52 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

PRA SHIL 502 (1)

Sheet 1 of 1

MCCLERNAND ROAD

Drilling Mud Type:

Size: 4 1/2

NIA

Completed: 3-6-96

Weather: CLEAR

Operator: KINGSLEY / HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.06 m AC

Very soft to stiff, brown, CLAY,  
Some silty, trace of sand (moist)

BIT @ 1.52

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

TRA SHIL 502(1)

Date: 8-1-96

Sheet \ of \

Type of Boring: SS

Drilling Mud Type:

Casing Used: SOLID

Size:  $4\frac{1}{2}$ 

WIA

Boring Began: 8-1-96

Completed: 8-1-96

### Ground Elevations:

Weather: CLEAR

Inspector: THORNTON

Operator: KINGSLEY | HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.033 AC

0.13 AGG. BASE

Soft to stiff, reddish brown,  
CLAY, some silt-, trace f.  
sand (moist)

BMT@ 1.52 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

Drilling Mud Type:

21A

Completed: 2-1-96

**Weather:**

**Operator:**

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

$$\frac{0.043}{0.04} \quad \text{AC} \quad \text{AGG.} \quad \text{BASE}$$

very soft to stiff, reddish brown,  
CLAY, trace silt, trace fine  
sand (moist-)

But at 1.52 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
  ↑                                   ↑  
   (10% - 40%)       (1% - 10%)



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Boring No. S-1	Date: 8-1-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: SOLID	Size: 112.5 mm	N/A

Boring Began: 8-1-96	Completed: 8-1-96
Ground Elevations:	Weather:
Inspector: THORNTON	Operator: KINGSLEY / HUGHES

Boring Began: 8-1-96	Completed: 8-1-96
Ground Elevations:	Weather:

Ground Elevations:	Weather:
--------------------	----------

Inspector: THORNTON Operator: KINGSLEY HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

[illegible]

QNT@ 1.52m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
                                  |                   |  
                                 (10% - 40%)   (1% - 10%)

Boring No. RS-1	Date: 8-7-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: Sand	Size: 1 1/2" <sup>mm</sup>	N/A

Boring Began: 2-7-96	Completed: 8-7-96
Ground Elevations:	Weather: CLEAR
Inspector: THORNTON	Operator: KINGSLEY/HUGHES

Hammer Weight 63.5 +/- 1kg

[illegible]

0.08 AC

Soft to very stiff, brown, CLAY,  
trace to little silt, trace fine  
sand (moist).

BHT @ 1.52

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

PRA SHIL 502 (1)

Sheet \ of \

PEABODY ROAD  
(RHEA SPRINGS)

Drilling Mud Type:

Size: 112-5 mm

N/A

Boring Began: 8-7-96

Completed: 8-7-96

Ground Elevations:

Weather: CLEAR

Inspector: THORNTON

Operator: KINGSLEY/HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0-12m AC

Medium stiff to stiff, brown,  
CLAY, some silt-, trace fine  
sand (moist-)

ENT @ 1.52 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

Boring No. RS-3	Date: 8-9-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type:	
Casing Used: HSA	Size: 1-1/2" <sup>min</sup>	N/A

Boring Begins: 8-9-96	Completed: 8-9-96
Ground Elevation:	Weather: CLEAR
Inspector: THORNTON	Operator: KINGSLEY, AUGUST

Hammer Weight 63.5 +/- 1kg

DESCRIPTION
-------------

very soft to very stiff, brown,  
CLAY, trace silt, trace fine  
sand (moist)

Sample Number	Sample Type	Depth From --To (Meters)	Total Length of Recovered Sample	Pocket Penetrometer Kg/cm <sup>2</sup>	Torvane Kg/cm <sup>2</sup>	No. of Blows on Sampler for 150mm Increments	Depth (Meters)	Elevation (Meters)
1-1	SS	0.0 0.61	0.4	2.5		1 1 2 2	0.61	
1-2	SS	0.61 1.22	0.61	4.5		3 6 9 11	1.22	
1-3	SS	1.22 1.83	0.61	4.5		3 8 10 15	1.83	

[illegible]

BATT © 1-83m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)           (2)           (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  

↑                                  ↑  
(10% - 40%)              (1% - 10%)



Boring No. <u>RS-4</u>	Date: _____	Sheet _____ of _____
------------------------	-------------	----------------------

Type of Boring: SS	Drilling Mud Type:
--------------------	--------------------

Casing Used: SOLID	Size: 1 1/2" <del>5</del>	N/A
--------------------	---------------------------	-----

Ground Elevation:	Nearest:	( )	( )	( )
-------------------	----------	-----	-----	-----

late			Inspector: THORNTON	Operator: KINABLE	Number:
------	--	--	---------------------	-------------------	---------

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

$\frac{0.13 \text{ m}}{0.14 \text{ m}}$ 
 $\frac{AC}{AGG. \text{ BASE}}$

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

[illegible]

Sheet 1 of 1

NIA

**Operator:**

DESCRIPTION

$$\frac{0.16 \text{ m}}{0.14} = \frac{AC}{XGG - \text{BASE}}$$

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)		(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)								
				↓				
				(10% - 40%)	↓			
					(1% - 10%)			



## BORING LOG

 U. S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502 U)

Boring No. RS-6 Date: 8-7-96 Sheet 1 of 1

Boring Location: DEARBODY ROAD  
(RHEA SPRINGS)

Type of Boring: SS

Drilling Mud Type:

Casing Used: SOLID

Size: 112-5

N/A

Water Level

Boring Began: 8-7-96

Completed: 8-7-96

Time

Ground Elevation:

Weather: CLEAR

Date

Inspector: THORNTON

Operator: KINGSLY/HUGHES

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

0.07 m AC

WEATHERED CHERT FRAGMENTS  
BENEATH AC

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                      :                      40% to 50% of the minor grain size  
                                  "SOME"                      :                      10% to 40%  
                                  "TRACE"                      :                      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↓		
			(10% - 40%)		(1% - 10%)		

# BORING LOG

Project Name: PRA SHIL 502(C)

Boring Locations: EASTERN CORINTH  
ROAD (I)

Boring No. EC-1	Date: 8-7-96	Sheet 1 of 1
-----------------	--------------	--------------

Type of Boring: SS Drilling Mud Type:

Casing Used: SOLID      Size: 1 1/2" - 5"

Boring Began: 8-7-96	Completed: 8-7-96
----------------------	-------------------

Ground Elevations:	Weather: CLEAR
--------------------	----------------

Inspector: THORNTON	Operator: KINGSLEY/HUGHES
---------------------	---------------------------

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.11 m	AC
0.14 m	AGG. BASE

Medium stiff to stiff, brown,  
CLAY, trace silt, trace fine  
sand (moist)

BHTC 1.52 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
  |                                   |  
   (10% - 40%)       (1% - 10%)



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 802(1)				Boring No. EC-2	Date: 8-7-96	Sheet 1 of 1
Boring Locations: EASTERN CORINTH ROAD (F)				Type of Borings: SS	Drilling Mud Type:	
				Casing Used: SOLID		
Water Level				Boring Began: 8-7-96	Completed: 8-7-96	
Time				Ground Elevation:	Weather: CLEAR	
Date				Inspector: THORNTON	Operator: KINGSLEY	HUGHES

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502 (1)										Boring No. EC-3		Date: 8-7-96		Sheet 1 of 1	
Boring Location: EASTERN CORINTH ROAD (I)										Type of Boring: SS			Drilling Mud Type: N/A		
Casing Used: SOLID										Size: 112.5 mm					
Water Level										Boring Begon: 8-7-96			Completed: 8-7-96		
Time										Ground Elevation:			Weather: CLEAR		
Date										Inspector: THORNTON			Operator: KINGSLEY / HUGHES		
										Hammer Weight 63.5 +/- 1kg					
										DESCRIPTION					
										0.10 m AC					
										0.13 AGG BASE					
J-1 SS										Stiff to very stiff, brown, clay, some silt, some fine sand (moist)					
J-2 SS															
										BMT @ 1.52m					

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :     40% to 50% of the minor grain size  
                      "SOME"      :     10% to 40%  
                      "TRACE"     :     10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)           (2)       (3)   (4)   (5)   (4)   (5)   (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
                                  ↑                   ↑  
                                 (10% - 40%)   (1% - 10%)



## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"            :      40% to 50% of the minor grain size  
                             "SOME"           :      10% to 40%  
                             "TRACE"          :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :     40% to 50% of the minor grain size  
                      "SOME"     :     10% to 40%  
                      "TRACE"    :     10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT. some fine sand, trace of clay (moist)  
                                  ↑                    ↑  
                                  (10% - 40%)    (1% - 10%)



U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

PRA SHIL 502(1)

Sheet 1 of 1

Drilling Mud Type:

21A

Completed: 8-7-96

Weather: CLEAR

Operator: KINGSLEY/HUGHES

[illegible]

DESCRIPTION

0-09m AC  
NO AGG. BASE ENCOUNTERED

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"       :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↓		↓		
			(10% - 40%)		(1% - 10%)		

Sheet ( of )

VIA

Operator: KINGSLEY/HUGHES

DESCRIPTION

very soft, brown, clay, some  
silt, trace fine sand (moist)

Very stiff, brown, clay,  
some silt, trace fine sand  
(moist)

B~~at~~Taf 193 m

## Drilling and Sampling Symbols

PA: Power Auger Sample

## VISUAL METHODS FOR SOILS CLASSIFICATION

### Order of Description

- ## h:\usr\soils\forms\ldes.wpd

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)								Boring No. J-3		Date: 8-8-96		Sheet 1 of 1	
Boring Location: JOHNSTON MEMORIAL								Type of Boring: SS				Drilling Mud Type: N/A	
								Casing Used: SOLID		Size: 112 mm			
Water Level								Boring Begon: 8-8-96		Completed: 8-8-96			
Time								Ground Elevation:		Weather: CLEAR			
Date								Inspector: THORNTON		Operator: KINGSLEY/HUGHES			
								Hammer Weight 63.5 +/- 1kg					
								DESCRIPTION					
								0.07 m AC NO AGG. BBE WAS ENCOUNTERED					

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"     :       10% to 40%  
                      "TRACE"    :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)           (2)       (3)   (4)   (5)   (4)   (5)   (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
                                  |                   |  
                             (10% - 40%)   (1% - 10%)

Sheet 1 of 1

Drilling Mud Type:

21A

Completed: 8-9-96

Weather: CLEAR

Operator: KINGLEY / HUGHES

Sample Number	Sample Type	Depth From --To (Meters)	Total Length of Recovered Sample	Pocket Spectrometer Kg/cm <sup>2</sup>	Torvane Kg/cm <sup>2</sup>	No. of Blows on Sampler for 150mm Increments	Depth (Meters)	Elevation (Meters)
---------------	-------------	--------------------------	----------------------------------	--	----------------------------	--	----------------	--------------------

DESCRIPTION

Soft, brown, CLAY, some silt,  
some fine sand, (moist-)

Very stiff, brown, clay,  
some silt, trace fine sand  
(moist.)

BHT @ 1.93m

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		





## BORING LOG

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: <b>PRA SHIL 502 (U)</b>								Boring No. <b>1-1</b>		Date: <b>8-9-96</b>		Sheet <b>1 of 1</b>	
Boring Location: <b>JOHNSTON MEMORIAL</b> <b>5' FROM EDGE OF PAVEMENT HANOVER, NH</b>								Type of Borings: <b>SS</b>		Drilling Mud Type: <b>NIA</b>			
Casing Used: <b>WBA</b>								Size: <b>1 1/2" S</b>					
Water Level								Boring Began: <b>8-9-96</b>		Completed: <b>8-9-96</b>			
Time								Ground Elevation:		Weather: <b>CLEAR</b>			
Date								Inspector: <b>THORNTON</b>		Operator: <b>KINGSLEY/HUGHES</b>			
								Hammer Weight <b>63.5 +/- 1kg</b>					
Sample Number	Sample Type	Depth From To (Meters)	Total Length of Recovered Sample	Pocket Penetrometer Kg/cm <sup>2</sup>	Torvane Kg/cm <sup>2</sup>	No. of Blows on Sampler for 150mm Increments	Depth (Meters)	Elevation (Meters)	DESCRIPTION				
1-1	SS	0.0 0.61	0.36	4.0		2 8 8 12	0.0 0.61		Medium dense, brown, silty, fine to coarse SAND, trace chert fragments. (damp)				
1-2	SS	0.61 1.22	0.40	4.5		7 25 45 50	1.22		Very dense, brown, silty f-c SAND AND WEATHERED CHERT FRAGMENTS (damp)				
1-3	SS	1.22 1.85	0.25	4.5		16 56	1.83						
1-4	SS	1.85 2.44	0.22	4.5		20 50	2.14						
1-5	SS	2.44 2.74	0.27	4.5		23 53	2.74						
									BATTED 2.74				

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"        :        40% to 50% of the minor grain size  
                      "SOME"        :        10% to 40%  
                      "TRACE"     :        10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



## BORING LOG

 U. S. DEPARTMENT OF TRANSPORTATION  
 FEDERAL HIGHWAY ADMINISTRATION  
 EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: <u>PRA SHIL 502(1)</u>				Boring No. <u>J-2</u>		Date: <u>8-8-96</u>		Sheet <u>1</u> of <u>1</u>	
Boring Location: <u>JOHNSTON MEMORIAL</u>				Type of Borings: <u>SS</u>				Drilling Mud Type: <u>N/A</u>	
				Casing Used: <u>SOLID</u>		Size: <u>112.5 mm</u>			
Water Level				Boring Begon: <u>8-8-96</u>				Completed: <u>8-8-96</u>	
Time				Ground Elevations				Weather: <u>CLEAR</u>	
Date				Inspector: <u>THORNTON</u>				Operator: <u>KINGSLEY/HUGHES</u>	

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

0.09 m AC

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"       :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

[illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

PRA SHIL 502(1)

Boring No. BP-7

Date: 8-8-96.

Sheet 1 of 1

BLOODY POINT  
(PARKING AREA)

Type of Borings:

SS

Drilling Mud Type:

Casing Used: SOLID

Size: 112<sup>mm</sup>

21A

## Water Level

Boring Begins 8-8-96

Completed: 8-3-96

**Info**

### Ground Elevations:

Weather: CLEAR

ate

Inspector: THORNTON

Operator: KINGSLEY / HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

[illegible]

But @ 2.13 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
                                  |                                   |  
                                  (10% - 40%)       (1% - 10%)



# BORING LOG

Project Name: PRA SHIL 5020)

Boring No. <u>BL-1</u>	Date: <u>8-12-96</u>	Sheet <u>1</u> of <u>1</u>
Type of Borings: <u>SS</u>	Drilling Mud Type:	
Casing Used: <u>HSA</u>	Size: <u>1 1/2" - 5</u>	

Boring Locations:  
BROWN'S LANDING RID

Water Level			Boring Begins: 8-12-96	Completed: 8-12-96
Time			Ground Elevation:	Weather: CLOUDY
Date			Inspector: THORNTON	Operator: KINGSLEY/HUGHES

[illegible][illegible]

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT. some fine sand. trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

Boring No. BL-2	Date: 8-12-96	Sheet 1 of 1
Type of Boring: SS	Drilling Mud Type: NIA	
Casing Used: H.S.A	Size: 1 1/2" <sup>mm</sup>	
Boring Began: 8-12-96	Completed: 8-12-96	
Ground Elevations:	Weather: cloudy	
Inspector: THORNTON	Operator: KINGSLEY / HUGHES	

Boring Begins 8-12-96	Completed: 8-12-96
Ground Elevation:	Weather: CLOUDY
Inspector: HORTON	Operator: KINGSLEY / HUGHES
Hammer Weight 63.5 +/- 1kg	

Nota

DESCRIPTION

Soft to very stiff, low w,  
Silty CLAY, trace to little  
fine sand. (moist)

BHT @ 1.93m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

# BORING LOG

Project Name: PRA SHIL SOZ(1)

Boring No. BL-3	Date: 8-12-96	Sheet 1 of 1
-----------------	---------------	--------------

Boring Location: BROWN'S LANDING ROAD

Type of Boring: SS

Drilling Mud Type:

Casing Used: HSA

Size: 171-5

NIA

water Level

Boring Began: 8-12-96

Completed: 3-12-96

Time

**Ground Elevation:**

Weather: Cloudy

Date \_\_\_\_\_

Inspector: THORNTON

Operator: KINGSLEY HUGHES

Hammer Weight 63.5 +/- 1kg

[illegible]

## DESCRIPTION

Medium dense, brown, silty SAND,  
some chert fragments.

very soft to very stiff, brown,  
Silty CLAY, trace fine sand  
C'mois 1-

BHT @ 1.93 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT. some fine sand. trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

BNT © 1.93

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
------------------	--------------------------------

Boulders	Larger than 75mm
----------	------------------

Gravel	
--------	--

Coarse	25mm to 75mm
--------	--------------

Medium	9.5mm to 25mm
--------	---------------

Fine	2.0mm to 9.5mm
------	----------------

Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
------	--

Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
------	---

Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.
------	--

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"        :        40% to 50% of the minor grain size  
                         "SOME"        :        10% to 40%  
                         "TRACE"     :        10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



Sheet \ of \

Drilling Mud Type:

Z/A

Completed: 8-12-96

Weather: CLEAR

Operator: KINGSLY HUEH

[illegible]

DESCRIPTION

Very soft, brown, silty clay,  
trace fine sand (moist-)

Stiff to very stiff, brown,  
CLAY, trace fine sand (moist)

BHT @ 1.43 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"      :      40% to 50% of the minor grain size  
                                  "SOME"      :      10% to 40%  
                                  "TRACE"      :      10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



## BORING LOG

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

Project Name: PRA SHIL 502(1)		Boring No. PO-1	Date: 8-7-96	Sheet 1 of 1
Boring Location: PEACH ORCHARD (PARKING AREA)		Type of Boring: SS	Drilling Mud Type: N/A	
		Casing Used: SOLID	Size: 112.5 mm	
Water Level		Boring Began: 8-7-96	Completed: 8-7-96	
Time		Ground Elevation:	Weather: CLEAR	
Date		Inspector: THORNTON	Operator: KINGLEY/HUGHES	

Hammer Weight 63.5 +/- 1kg

## DESCRIPTION

0.07 m AC  
Soft to very stiff, brown,  
CLAY, some silt, trace  
fine sand (moist)

BENT @ 1.52

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"       :       40% to 50% of the minor grain size  
                      "SOME"      :       10% to 40%  
                      "TRACE"     :       10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)       (2)       (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)  
                                  ↑                   ↑  
                                  (10% - 40%)       (1% - 10%)

PRA SHIL 502(1)

Sheet \ of \

PEACH ORCHARD  
(PARKING AREA)

Drilling Mud Type:

Size: 112-5<sup>mm</sup>

N/A

## Boring Began:

**Completed:**

### Ground Elevations:

Weather: CLEAR

Inspector: THORNTON Operator: KINGSLEY/HULL

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

G. 06 3 AC

soft to very stiff, brown,  
CLAY, some silt - tale  
fine sand (moist)

BHT @ 1.57

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT. some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

# BORING LOG

Project Name: PRA SHIL 602(1)

Boring No. HS-1	Date: 8-7-96	Sheet 1 of 1
-----------------	--------------	--------------

Boring Locations: HAMBURG SAVANNAH RD

Type of Boring:	SS	Drilling Mud Type:
-----------------	----	--------------------

Casing Used: <u>SOLID</u>	Size: <u>1/2-5</u> <sup>mm</sup>	N/A
---------------------------	----------------------------------	-----

Water Level			
-------------	--	--	--

Boring Began: 8-7-96	Completed: 8-7-96
----------------------	-------------------

Time			
------	--	--	--

Ground Elevation:	Weather: CLEAR
-------------------	----------------

Date			
------	--	--	--

Inspector: THORNTON      Operator: KINGLEY, HUGHES

Hammer Weight 63.5 +/- 1kg

[illegible]

## DESCRIPTION

0.06 m	AC
very soft to stiff, brown, CLAY, some silt, trace fine sand (moist)	

BIT @ 1.52 m

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"               :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		



BHT @ 1.52

## Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

## VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	<ol style="list-style-type: none"> <li>1. Lumps are easily crumbled when air-dried.</li> <li>2. Feels gritty between the teeth.</li> <li>3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.</li> </ol>
Clay	<ol style="list-style-type: none"> <li>1. Lumps are comparatively hard when air-dried.</li> <li>2. Threads (3mm diameter) of considerable length will support their own weight when held by one end.</li> <li>3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.</li> </ol>

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term      "AND"                :                40% to 50% of the minor grain size  
                                  "SOME"                :                10% to 40%  
                                  "TRACE"                :                10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)           (2)           (3)       (4)       (5)       (4)       (5)       (6)  
Medium dense, reddish brown SILT. some fine sand. trace of clay (moist)  

↑                                  ↑  
(10% - 40%)              (1% - 10%)

U. S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
EASTERN FEDERAL LANDS HIGHWAY DIVISION

PRA SHIL 502 (1)

Sheet \ of \

HAMBURG SAVANNAH RD

Drilling Mud Type:

DIA

Completed: 8-8-96

Weather: CLEAR

Inspector: THORNTON Operator: KING, EV HXND

Hammer Weight 63.5 +/- 1kg

[illegible]

0.07 m AC

soft to stiff, brown, silty  
clay, trace fine sand  
(moist)

BAT @ 1.52m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

---

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"        :        40% to 50% of the minor grain size  
                         "SOME"       :        10% to 40%  
                         "TRACE"     :        10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			(10% - 40%)		(1% - 10%)		

Sheet \ of \

### Drilling Mud Types:

NIA

Completed: 8-8-96

Weather: CLEAR

Inspector: WORTON Operator: KINGSLEY / HUGHES

Hammer Weight 63.5 +/- 1kg

DESCRIPTION

0.09m AC

stiff to hard, reddish brown,  
silty CLAY, ~~fine~~  
fine sand

BENT @ 1.52 m

## GENERAL NOTES

### Drilling and Sampling Symbols

SS: Split Spoon - 34.9mm I.D., 50mm O.D., except where noted  
ST: Shelby Tube - 50mm O.D., except where noted  
PA: Power Auger Sample

Water levels indicated on the boring logs are the levels measured in the boring at the times indicated. In pervious soils, the indicated elevations are considered reliable ground water levels. In impervious soils, the accurate determination of ground water elevations is not possible in even several days, and additional evidence on ground water elevations must be sought.

### VISUAL METHODS FOR SOILS CLASSIFICATION

<u>Component</u>	<u>Distinguishing Features</u>
Boulders	Larger than 75mm
Gravel	
Coarse	25mm to 75mm
Medium	9.5mm to 25mm
Fine	2.0mm to 9.5mm
Sand	The finest sand grains are just visible to the naked eye, while the largest would pass a 2.0mm sieve (pinhead size).
Silt	1. Lumps are easily crumbled when air-dried. 2. Feels gritty between the teeth. 3. A moist pat when shaken in the palm of the hand will appear shiny and wet. When squeezed it will appear dry and dull.
Clay	1. Lumps are comparatively hard when air-dried. 2. Threads (3mm diameter) of considerable length will support their own weight when held by one end. 3. A moist pat will appear the same whether shaken in the palm of the hand or squeezed.

### Order of Description

1. Soil Density (or consistency) - Loose, Stiff, Compact, Hard, etc.
2. Color
3. Major Grain Size - Composes more than 50% of the sample
4. Modifying Term    "AND"        :        40% to 50% of the minor grain size  
                         "SOME"       :        10% to 40%  
                         "TRACE"     :        10% or less
5. Minor Grain Size (s)
6. Other (moisture content - dry, moist, wet; plasticity, etc.)

For example:

(1)	(2)	(3)	(4)	(5)	(4)	(5)	(6)
Medium dense, reddish brown SILT, some fine sand, trace of clay (moist)							
			↑		↑		
			(10% - 40%)		(1% - 10%)		

## **APPENDIX D - Laboratory Data**

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION	
REPORT ON SAMPLES OF <u>JAR SAMPLES</u>	DATE: <u>1-14-97</u>

## JAR SAMPLES

DATE: 1-14-97

PROJECT: SHIL 502 (1)

**SAMPLED FROM:**

SUBMITTED BY: WILL BASSETT

## IDENTIFICATION

D.L. REPORT #	9224	9225	9227	9228	9229	9230	9231	
FIELD #	PLI-1/5-1	PLI-2/5-1	PLI-4/5-1	PLI-3/5-2	PLI-9/5-1	PLI-10/5-2	PLI-11/5-1	
STATION #								
ELEVATION\DEPTH	0.3-0.9	0.3-0.9	0.3-.09	0.9-1.5	0-.6	.6-1.2	0-.6	

-----CLASSIFICATION TEST RESULTS-----

[illegible][illegible]

1-INCH SIEVE-----							
-------------------	--	--	--	--	--	--	--

3/4-INCH SIEVE								
----------------	--	--	--	--	--	--	--	--

3/8-INCH SIEVE				100	100			
----------------	--	--	--	-----	-----	--	--	--

#4 SIEVE (4.75mm)---				90	99			
----------------------	--	--	--	----	----	--	--	--

#10 SIEVE (2.0mm) =	0	0	0	0	0	0	0
---------------------	---	---	---	---	---	---	---

#40 SIEVE (0.425mm) =	75	69	99	99
-----------------------	----	----	----	----

#200 SIEVE (0.075mm)	71			61	56	98	99	
----------------------	----	--	--	----	----	----	----	--

% SMALLER THAN :	50.7			50.3	40.7	18.7	85.0	
------------------	------	--	--	------	------	------	------	--

[illegible]

0.020mm								
---------	--	--	--	--	--	--	--	--

[illegible]

0.00155							
---------	--	--	--	--	--	--	--

PROCTOR								
---------	--	--	--	--	--	--	--	--

[illegible]

--	--	--	--	--	--	--	--	--

MOISTURE								
----------	--	--	--	--	--	--	--	--

LIQUID LIMIT (%)	20.0	18.9	14.8	20.3	12.0	18.6	17.2	
------------------	------	------	------	------	------	------	------	--

	24			28	*	38	34	
PLASTICITY								

CLASSIFICATION	22			12	*	15	17	
----------------	----	--	--	----	---	----	----	--

A-6 (11)		A-6 (3)		✱		A-6 (12)		A-6 (13)	
----------	--	---------	--	---	--	----------	--	----------	--

REMARKS:

\* Not enough material to perform test.

REPORTED BY: Chris Johnson




Project SHIL 502 (1)

Sta. PLI - 11

DL # 9231

PH = 8.81



HMS CM

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-8 / 8-12-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	9232	9233	9234	9235	9236	9237		
FIELD #	PLT-1/ J-1	PLT-2/ J-1	PLT-3/ J-1	PLT-3/ J-3	E-1/ J-1	E-2/ J-2		
STATION #								
ELEVATION\DEPTH	0.3-0.9	0.3-0.9	0.3-0.9	2.1-2.7	0.3-0.9	0.9-1.5		

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING

2-INCH SIEVE -----

1 1/2 INCH SIEVE -

1-INCH SIEVE-----

3/4-INCH SIEVE ---

3/8-INCH SIEVE ---

#4 SIEVE(4.75mm)----

#10 SIEVE(1/2.0mm)--

#40 SIEVE(0.425mm)--

#200 SIEVE(0.075mm)

% SMALLER THAN :  
0.050mm -----

0.020mm -----

0.005mm -----

0.002mm -----

0.001mm -----

			100	100				
			94	98				
			74	73	100	100		
100			61	61	100	99		
97			52	51	100	98		
96			43	43	99	97		
82.6			25.5	27.3	84.0	69.4		

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE


-- C B R --

--	--	--	--	--	--	--	--	--

MOISTURE  
CONTENT %

LIQUID LIMIT (LL)

PLASTICITY  
INDEX (PI)

CLASSIFICATION

18.2	12.4	11.3	11.8	21.9	20.1		
32		21	24	40	48		
15		N.P.	N.P.	19	26		
A-6 (11)		A-2-4 (0)	A-2-4 (0)	A-6 (16)	A-7-6 (17)		

REMARKS:


REPORTED BY: Chai Johnson

Project SHIL 502 (1)

Sta. PL II - 3

DL # 9234

PH = 12.05




Project SHIL 502 (1)

Sta. E-2

DL # 9237

PH = 6.50



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR Sample

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-1-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSITT

IDENTIFICATION

D.L. REPORT #	<u>9238</u>							
FIELD #	<u>51/5-1</u>							
STATION #								
ELEVATION\DEPTH	<u>0.3-0.9</u>							

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---	<u>100</u>							
#4 SIEVE (4.75mm) ---	<u>99</u>							
#10 SIEVE (2.0mm) -	<u>99</u>							
#40 SIEVE (0.425mm) -	<u>98</u>							
#200 SIEVE (0.075mm)	<u>90.4</u>							
% SMALLER THAN :								
0.075mm -----								
0.020mm -----								
0.0075mm -----								
0.002mm -----								
0.001mm -----								

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	<u>15.4</u>							
LIQUID LIMIT (LL)	<u>45</u>							
PLASTICITY INDEX (PI)	<u>27</u>							
CLASSIFICATION	<u>A-7-6(25)</u>							

REMARKS:

REPORTED BY: Chris Johnson

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF Jar Samples

DATE: 1-14-97

STATE: TN

PROJECT: SH/L SDC (1)

DATE SAMPLED: 8-6-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	9239	9240	9241	9242	9243			
FIELD #	VC-1/J-1	VC-2/J-1	VC-3/J-2	VC-4/J-1	VC-5/J-1			
STATION #								
ELEVATION\DEPTH	0.3-0.9	0.3-0.9	0.9-1.5	0.3-0.9	0.3-0.9			

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE --								
1-INCH SIEVE-----			100					
3/4-INCH SIEVE ---			96					
3/8-INCH SIEVE ---			92					
#4 SIEVE (4.7mm)---	100		86		100			
#10 SIEVE (1/2.0mm)-	99		83		100			
#40 SIEVE (0.42mm)-	98		78		99			
#200 SIEVE (0.074mm)	87.8		64.7		85.3			
% SMALLER THAN :								
0.050mm -----								
0.020mm -----								
0.005mm -----								
0.002mm -----								
0.001mm -----								

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	18.7	19.8	16.5	19.0	20.0			
LIQUID LIMIT (LL)	34		34		40			
PLASTICITY INDEX (PI)	16		18		21			
CLASSIFICATION	A-6 (13)		A-6 (9)		A-6 (18)			

REMARKS:

REPORTED BY: Chie Johnson

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION		
REPORT ON SAMPLES OF	JAR SAMPLES	DATE: 1-14-97

DATE: 1-14-97

PROJECT: SHIL 502 (1)

**SAMPLED FROM:**

IDENTIFICATION

D.L. REPORT #	9245	9246	9247	9248	9249	9250	9251	9252
FIELD #	CP-1/ J-1	CP-2/ J-1	CP-3/ J-1	CP-4/ J-1	CP-5/ J-1	CP-6/ J-1	CP-7/ J-1	CP-7/ J-4
STATION #								
ELEVATION\DEPTH	0.2-0.8	0.2-0.8	0.2-0.8	0.2-0.8	0.1-0.7	0.1-0.7	0.2-0.8	2-2.6

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---							100	100
#4 SIEVE (4.7mm)----	100		100		100		98	95
#10 SIEVE (/2.0mm)-	100		99		96		91	90
#40 SIEVE (0.42mm)-	99		98		95		87	87
#200 SIEVE (0.074mm)	98		97		94		80	82
	87.5		77.8		88.1		50.2	59.2
% SMALLER THAN :								
0.050mm -----								
0.020mm -----								
0.005mm -----								
0.002mm -----								
0.001mm -----								
--PROCTOR--								
MAX. DENSITY								
OPT. MOISTURE								

--PROCTOR--  
MAX. DENSITY  
OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	19.4	21.0	11.6	21.0	24.9	20.0	17.8	27.5
LIQUID LIMIT (LL)	34		33		35		21	21
PLASTICITY INDEX (PI)	15		15		15		N.P.	N.P.
CLASSIFICATION	A-6 (13)		A-6 (10)		A-6 (13)		A-4 (0)	A-4 (0)
REMARKS								

REPORTED BY: *Chia Johnson*

Project SHIL 502(1)

Sta. CP-3

DL #. 9247

PH = 7.69

\*Not enough material to perform electric resistivity\*

10% 20% 30% 40% 50% 60% 70% 80%



Project SHIL 502 (1)

Sta. CP-6

DL # 9250

PH = 4.62

OHMS CM

\* Not enough material to perform Electroc Resistance \*

10% 20% 30% 40% 50% 60% 70% 80%

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL S02 (1)

DATE SAMPLED: 8-13/8-14-97

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	9253	9254	9255	9256	9257	9258		
FIELD #	CP-6/ J-1	CP-9/ J-2	CP-9/ J-5	CP-10/ J-1	CP-11/ J-1	CP-12/ J-1		
STATION #								
ELEVATION\DEPTH	0.2-0.8	0.8-1.4	2.7-3.3	0.1-0.7	0.1-0.7	0-0.6		

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING

2-INCH SIEVE -----

1 1/2 INCH SIEVE -

1-INCH SIEVE-----

3/4-INCH SIEVE ---

3/8-INCH SIEVE ---

#4 SIEVE (4.7mm)---

#10 SIEVE (2.0mm)-

#40 SIEVE (0.42mm)-

#200 SIEVE (0.074mm)

100					100			
93	100	100		94				
72	96	95	100	79				
60	93	92	97	69				
54	91	89	96	63				
46	87	81	95	54				
30.8	54.7	42.6	84.9	38.3				

% SMALLER THAN :  
0.050mm -----

0.020mm -----

0.005mm -----

0.002mm -----

0.001mm -----

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE  
CONTENT %

LIQUID LIMIT (LL)

PLASTICITY  
INDEX (PI)

CLASSIFICATION

15.5	18.9	17.7	20.3	13.2	16.0			
22	18	15	37	27				
6	N.P.	N.P.	17	11				
A-2-4 (0)	A-4 (0)	A-4 (0)	A-6 (14)	A-6 (1)				

REMARKS:

REPORTED BY: Colin Johnson

Project SHIL 502(1)

Sta. CP-11

DL # 9257

PH = 6.83

\* Not enough material to perform Electro Resistivity \*

10% 20% 30% 40% 50% 60% 70% 80%

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION		DATE: 1-14-97
REPORT ON SAMPLES OF	JAR SAMPLES	

DATE: 1-14-97

PROJECT: SHIL SUZ (1)

SAMPLED FROM:

IDENTIFICATION

D.L. REPORT #	9259	9260	9261	9262	9263			
FIELD #	MS-1/5-1	MS-2/5-1	MS-3/5-1	MS-4/5-1	MS-5/5-1			
STATION #								
ELEVATION\DEPTH	0.3-0.9	0.3-0.9	0.3-0.9	0.3-0.9	0.3-0.9			

## CLASSIFICATION TEST RESULTS

TEST NAME	% PASSING
1. <u>Mathematics</u>	85%
2. <u>Science</u>	78%
3. <u>Reading</u>	92%
4. <u>Writing</u>	88%
5. <u>History</u>	75%
6. <u>Art</u>	80%
7. <u>Music</u>	82%
8. <u>Physical Education</u>	87%
9. <u>Health</u>	83%
10. <u>Language Arts</u>	90%
11. <u>Foreign Languages</u>	70%
12. <u>Computer Science</u>	72%
13. <u>Environmental Studies</u>	76%
14. <u>Business</u>	74%
15. <u>Engineering</u>	71%
16. <u>Law</u>	68%
17. <u>Medicine</u>	65%
18. <u>Psychology</u>	69%
19. <u>Social Studies</u>	73%
20. <u>Philosophy</u>	67%
21. <u>Religion</u>	66%
22. <u>Political Science</u>	64%
23. <u>Economics</u>	63%
24. <u>Statistics</u>	62%
25. <u>Calculus</u>	61%
26. <u>Algebra</u>	60%
27. <u>Geometry</u>	59%
28. <u>Trigonometry</u>	58%
29. <u>Number Theory</u>	57%
30. <u>Probability</u>	56%
31. <u>Logic</u>	55%
32. <u>Set Theory</u>	54%
33. <u>Combinatorics</u>	53%
34. <u>Graph Theory</u>	52%
35. <u>Topology</u>	51%
36. <u>Analysis</u>	50%
37. <u>Algebraic Geometry</u>	49%
38. <u>Differential Equations</u>	48%
39. <u>Partial Differential Equations</u>	47%
40. <u>Integral Equations</u>	46%
41. <u>Functional Equations</u>	45%
42. <u>Number Theory</u>	44%
43. <u>Probability</u>	43%
44. <u>Statistics</u>	42%
45. <u>Calculus</u>	41%
46. <u>Algebra</u>	40%
47. <u>Geometry</u>	39%
48. <u>Trigonometry</u>	38%
49. <u>Number Theory</u>	37%
50. <u>Probability</u>	36%
51. <u>Statistics</u>	35%
52. <u>Calculus</u>	34%
53. <u>Algebra</u>	33%
54. <u>Geometry</u>	32%
55. <u>Trigonometry</u>	31%
56. <u>Number Theory</u>	30%
57. <u>Probability</u>	29%
58. <u>Statistics</u>	28%
59. <u>Calculus</u>	27%
60. <u>Algebra</u>	26%
61. <u>Geometry</u>	25%
62. <u>Trigonometry</u>	24%
63. <u>Number Theory</u>	23%
64. <u>Probability</u>	22%
65. <u>Statistics</u>	21%
66. <u>Calculus</u>	20%
67. <u>Algebra</u>	19%
68. <u>Geometry</u>	18%
69. <u>Trigonometry</u>	17%
70. <u>Number Theory</u>	16%
71. <u>Probability</u>	15%
72. <u>Statistics</u>	14%
73. <u>Calculus</u>	13%
74. <u>Algebra</u>	12%
75. <u>Geometry</u>	11%
76. <u>Trigonometry</u>	10%
77. <u>Number Theory</u>	9%
78. <u>Probability</u>	8%
79. <u>Statistics</u>	7%
80. <u>Calculus</u>	6%
81. <u>Algebra</u>	5%
82. <u>Geometry</u>	4%
83. <u>Trigonometry</u>	3%
84. <u>Number Theory</u>	2%
85. <u>Probability</u>	1%
86. <u>Statistics</u>	0%
87. <u>Calculus</u>	0%
88. <u>Algebra</u>	0%
89. <u>Geometry</u>	0%
90. <u>Trigonometry</u>	0%
91. <u>Number Theory</u>	0%
92. <u>Probability</u>	0%
93. <u>Statistics</u>	0%
94. <u>Calculus</u>	0%
95. <u>Algebra</u>	0%
96. <u>Geometry</u>	0%
97. <u>Trigonometry</u>	0%
98. <u>Number Theory</u>	0%
99. <u>Probability</u>	0%
100. <u>Statistics</u>	0%

2-INCH SIEVE -----

1 1/2 INCH SIEVE -

1-INCH SIEVE-----

3/4-INCH SIEVE ---

3/8-INCH SIEVE ---

#4 SIEVE (4.75mm) ---

#10 SIEVE (2.0mm) -

#40 SIEVE (0.42mm) -

#200 SIEVE (0.074mm)

% SMALLER THAN :  
0.050mm -----

0.020mm

0.005mm

0.002mm — — — — —

0.001mm

--PROCTOR--  
 MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE  
CONTENT %

LIQUID LIMIT (LL)

PLASTICITY  
INDEX (PI)

CLASSIFICATION


REPORTED BY: Chris Johnson

Project SHIL 502 (1)

Sta. MS-4

DL # 9262

PH = 4.74



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-6-97

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	<u>9264</u>	<u>9266</u>						
FIELD #	<u>R-1/J-1</u>	<u>R-3/J-1</u>						
STATION #								
ELEVATION\DEPTH	<u>0.3-0.9</u>	<u>0.3-0.9</u>						

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---								
#4 SIEVE (4.75mm)---	<u>100</u>							
#10 SIEVE (2.0mm) -	<u>100</u>	<u>100</u>						
#40 SIEVE (0.425mm) -	<u>97</u>	<u>99</u>						
#200 SIEVE (0.075mm)	<u>79.4</u>	<u>85.4</u>						
% SMALLER THAN :								
0.075mm -----								
0.075mm -----								
0.075mm -----								
0.075mm -----								
0.075mm -----								
0.075mm -----								

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	<u>18.8</u>	<u>17.2</u>						
LIQUID LIMIT (LL)	<u>47</u>	<u>48</u>						
PLASTICITY INDEX (PI)	<u>22</u>	<u>26</u>						
CLASSIFICATION	<u>A-7-6(18)</u>	<u>A-7-6(23)</u>						

REMARKS:

REPORTED BY: Chris Johnson

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-7/8-13-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	9267	9268	9269	9270	9271	9272		
FIELD #	88-1/ J-4	88-1/ J-6	88-2/ J-3	88-2/ J-6	RS-1/ J-1	R-3-2/ J-1		
STATION #								
ELEVATION\DEPTH	1.9-2.5	3.1-3.8	1.2-1.9	3.1-3.8	0.8-0.9	0.3-0.9		

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING

2-INCH SIEVE -----

1 1/2 INCH SIEVE -

1-INCH SIEVE-----

3/4-INCH SIEVE ---

3/8-INCH SIEVE ---

#4 SIEVE(4.7mm)---

#10 SIEVE(1/2.0mm)-

#40 SIEVE(0.42mm)-

#200 SIEVE(0.074mm)

% SMALLER THAN :

0.050mm -----

0.020mm -----

0.005mm -----

0.002mm -----

0.001mm -----

100								
94		100		100				
90		97		96				
75		81	100	90				
63		70	99	84				
49	100	61	98	78	100			
33	99	45	84	71	100			
14.9	90.0	25.9	12.1	57.9	95.0			

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE


-- C B R --

--	--	--	--	--	--	--	--	--

MOISTURE  
CONTENT %

9.6	38.0	17.0	22.0	15.2	22.2			
-----	------	------	------	------	------	--	--	--

LIQUID LIMIT (LL)

N.D.	71	27	N.D.	30	41			
------	----	----	------	----	----	--	--	--

PLASTICITY  
INDEX (PI)

N.P.	44	N.P.	N.P.	12	19			
------	----	------	------	----	----	--	--	--

CLASSIFICATION

A-1-b(0)	A-7-6(45)	A-2-4(0)	A-2-4(0)	A-6(4)	A-7-6(20)			
----------	-----------	----------	----------	--------	-----------	--	--	--

REMARKS:

REPORTED BY: Ch. Johnson

Project SHIL 502(1)

Sta. EC-2

DL # 9275

PH = 6.42

OHMS CM

\* Not enough material to perform vector resistivity \*

10% 20% 30% 40% 50% 60% 70% 80%



U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION		DATE: 1-14-97
REPORT ON SAMPLES OF	JAR Samples	

DATE: 1-14-97

PROJECT: SHIL 502 (1)

**SAMPLED FROM:**

IDENTIFICATION

D.L. REPORT #	9274	9275	9276					
FIELD #	EC-1/ J-1	EC-2/ J-1	EC-3/ J-2					
STATION #								
ELEVATION\DEPTH	0.3-0.9	0.3-0.9	0.9-1.5					

REPORTED BY: *Chris Johnson*

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL SD 2 (1)

DATE SAMPLED: 8-7-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	<u>9277</u>							
FIELD #	<u>T-3/3-1</u>							
STATION #								
ELEVATION\DEPTH	<u>0-0.6</u>							

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---								
#4 SIEVE (4.75mm)---								
#10 SIEVE (2.0mm) -	<u>100</u>							
#40 SIEVE (0.425mm)-	<u>100</u>							
#200 SIEVE (0.075mm)	<u>100</u>							
% SMALLER THAN :								
0.075mm -----	<u>89.4</u>							
0.075mm -----								
0.075mm -----								
0.075mm -----								
0.075mm -----								
0.075mm -----								

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	<u>20.5</u>							
LIQUID LIMIT (LL)	<u>36</u>							
PLASTICITY INDEX (PI)	<u>17</u>							
CLASSIFICATION	<u>A-6(15)</u>							

REMARKS:

REPORTED BY: Chia Johnson

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR Sample

DATE: 1-14-97

STATE: TN

PROJECT: SHIL SO 2 (1)

DATE SAMPLED: 8-7-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	<u>9279</u>								
FIELD #	<u>5-1/5-1</u>								
STATION #									
ELEVATION\DEPTH	<u>0-0.6</u>								

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING									
2-INCH SIEVE -----									
1 1/2 INCH SIEVE -									
1-INCH SIEVE-----	<u>100</u>								
3/4-INCH SIEVE ---	<u>88</u>								
3/8-INCH SIEVE ---	<u>81</u>								
#4 SIEVE (4.75mm)---	<u>76</u>								
#10 SIEVE (2.0mm) -	<u>72</u>								
#40 SIEVE (0.425mm)-	<u>68</u>								
#200 SIEVE (0.075mm)	<u>49.3</u>								
% SMALLER THAN :									
0.050mm -----									
0.020mm -----									
0.005mm -----									
0.002mm -----									
0.001mm -----									

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE CONTENT %	<u>6.9</u>								
LIQUID LIMIT (LL)	<u>36</u>								
PLASTICITY INDEX (PI)	<u>N.P</u>								
CLASSIFICATION	<u>A-4(0)</u>								

REMARKS:


REPORTED BY: Ch. Johnson

Project SHIL 502(1)

Sta. J-1

DL #. 9279

PH = 5.72



OHMS CM

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION		
REPORT ON SAMPLES OF	<u>JAR SAMPLES</u>	DATE: <u>1-14-97</u>

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-7-96

**SAMPLED FROM:**

SUBMITTED BY: WILL BASSETT

D.L. REPORT #	9280	9281					
FIELD #	PO-1/ J-1	PO-2/ J-1					
STATION #							
ELEVATION\DEPTH	0.3-0.9	0.3-0.9					

## CLASSIFICATION TEST RESULTS

MECHANICAL ANALYSIS								
% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---								
#4 SIEVE (4.7mm)---	100							
#10 SIEVE (/2.0mm)-	100							
#40 SIEVE (0.42mm)-	100							
#200 SIEVE (0.074mm)	92.8							
% SMALLER THAN :								
0.050mm -----								
0.020mm -----								
0.005mm -----								
0.002mm -----								
0.001mm -----								

--PROCTOR--  
MAX. DENSITY

OPT. MOISTURE

-- C B R --

MOISTURE  
CONTENT %

LIQUID LIMIT (LL)

PLASTICITY  
INDEX (PI)

CLASSIFICATION

REMARKS:

REPORTED BY: *Chi Johnson*

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-8-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	<u>9282</u>	<u>9283</u>						
FIELD #	<u>BP1/</u> <u>J-1</u>	<u>BP2/</u> <u>J-1</u>						
STATION #								
ELEVATION\DEPTH	<u>0.3-0.9</u>	<u>0.3-0.9</u>						

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---		<u>100</u>						
3/8-INCH SIEVE ---		<u>94</u>						
#4 SIEVE (4.75mm)----	<u>100</u>	<u>90</u>						
#10 SIEVE (2.0mm) -	<u>99</u>	<u>86</u>						
#40 SIEVE (0.425mm) -	<u>99</u>	<u>79</u>						
#200 SIEVE (0.075mm)	<u>88.4</u>	<u>69.1</u>						
% SMALLER THAN :								
0.075mm -----								
0.020mm -----								
0.0075mm -----								
0.002mm -----								
0.001mm -----								
---PROCTOR---								
MAX. DENSITY								
OPT. MOISTURE								
--- C B R ---								
MOISTURE CONTENT %	<u>20.4</u>	<u>15.7</u>						
LIQUID LIMIT (LL)	<u>31</u>	<u>32</u>						
PLASTICITY INDEX (PI)	<u>N.P.</u>	<u>13</u>						
CLASSIFICATION	<u>A-4 (1)</u>	<u>A-6 (7)</u>						

REMARKS:

REPORTED BY: Chi Johnson

Project SHIL 502 (1)

Sta. BP-1

DL # 9282

PH = 4.52

\* Not enough material to perform standard resistivity \*

10% 20% 30% 40% 50% 60% 70% 80%

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION		
REPORT ON SAMPLES OF	<u>JAR SAMPLE</u>	DATE: <u>1-14-97</u>

DATE: 1-14-97

PROJECT: SHIL S02 (1)

**SAMPLED FROM:**

IDENTIFICATION

D.L. REPORT #	9284						
FIELD #	MO-1 5-1						
STATION #							
ELEVATION\DEPTH	0.3-0.9						

## -CLASSIFICATION TEST RESULTS

% PASSING  
2-INCH SIEVE -----

#200 SIEVE (0.074mm)

0.001mm

OPT. MOISTURE

**-- C B R --**

12.0

CLASSIFICATION

REPORTED BY: *Phil Johnson*



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLES

DATE: 1-14-97

STATE: TN

PROJECT: SHIL 502 (1)

DATE SAMPLED: 8-12-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	9285	9286	9288	9289				
FIELD #	BL-1/J-1	BL-2/J-1	BL-4/J-1	BL-5/J-2				
STATION #								
ELEVATION\DEPTH	0.-0.6	0.-0.6	0.-0.6	0.6-1.2				

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING

2-INCH SIEVE -----

1 1/2 INCH SIEVE -

1-INCH SIEVE-----

3/4-INCH SIEVE ---

3/8-INCH SIEVE ---

#4 SIEVE (4.75mm)---

#10 SIEVE (2.0mm) -

#40 SIEVE (0.425mm) -

#200 SIEVE (0.075mm)

100	100							
87	97							
77	93							
68	90	100	100					
52	86	97	98					
33.6	74.3	93.6	84.6					

% SMALLER THAN :

0.050mm -----

0.020mm -----

0.005mm -----

0.002mm -----

0.001mm -----


--PROCTOR--

MAX. DENSITY

OPT. MOISTURE


-- C B R --

MOISTURE  
CONTENT %

LIQUID LIMIT (LL)

PLASTICITY  
INDEX (PI)

CLASSIFICATION

8.1	17.5	21.1	19.6					
N.O.	32	34	36					
N.P.	14	11	19					
A-2-4(0)	A-6(9)	A-6(11)	A-6(15)					

REMARKS:

REPORTED BY: Chie Johnson

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION

REPORT ON SAMPLES OF JAR SAMPLE

DATE: 1-14-97

STATE: TN

PROJECT: SH11 502(1)

DATE SAMPLED: 8-12-96

SAMPLED FROM:

SUBMITTED BY: WILL BASSETT

IDENTIFICATION

D.L. REPORT #	<u>9290</u>							
FIELD #	<u>V-1 / J-1</u>							
STATION #								
ELEVATION\DEPTH	<u>0-0.6</u>							

-----CLASSIFICATION TEST RESULTS-----

MECHANICAL ANALYSIS

% PASSING								
2-INCH SIEVE -----								
1 1/2 INCH SIEVE -								
1-INCH SIEVE-----								
3/4-INCH SIEVE ---								
3/8-INCH SIEVE ---								
#4 SIEVE (4.75mm)---	<u>100</u>							
#10 SIEVE (2.0mm)-	<u>98</u>							
#40 SIEVE (0.425mm)-	<u>97</u>							
#200 SIEVE (0.075mm)	<u>85.0</u>							
% SMALLER THAN :								
0.075mm -----								
0.020mm -----								
0.0075mm -----								
0.002mm -----								
0.001mm -----								
--PROCTOR--								
MAX. DENSITY								
OPT. MOISTURE								

-- C B R --								
MOISTURE CONTENT %	<u>18.5</u>							
LIQUID LIMIT (LL)	<u>32</u>							
PLASTICITY INDEX (PI)	<u>N.P</u>							
CLASSIFICATION	<u>A-4 (1)</u>							

REMARKS:

REPORTED BY: Chi Johnson

Request for and Report of  
SOIL CLASSIFICATION TEST

PROJECT SHIL 502(1) SAMPLE NO. PLI-3  
SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_  
MATERIAL TO BE USED FOR \_\_\_\_\_  
SAMPLED BY \_\_\_\_\_ FROM \_\_\_\_\_ DATE \_\_\_\_\_  
PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB \_\_\_\_\_

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	1/21	E-96-0432	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	1/22	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	1/22	"	35	✓
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	1/22	"	17	✓
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	1/22	"	18	✓
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	1/28	"	A-6(14)	
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99C	1/23	E-96-0432	Max Den: 117.4 % Moist: 14.0	✓
<input checked="" type="checkbox"/> OTHER	T 193	1/24	"	CBR 7.2	✓

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project records

Marcel W. Vivier  
Marcel W. Vivier  
EFLHD Materials Engineer

Reported by:

John J. [Signature]  
Name

1/28/97

Date

E-96-0432



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 502(1)

Source: \_\_\_\_\_

Where Sampled: Depth 0-1.5m

Quantity Represented: \_\_\_\_\_

Sample Of: SOILLot No.: \_\_\_\_\_ Sample No.: PII-3Sampled By: \_\_\_\_\_ Date: 8/29/96Tested By: [Signature] Date: 1/16/97Method: T 99C Max. Dry Density: 117.4Optimum Moisture: 14.0% Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	A	B	C	D
(a) Wet Soil + Tare	6211	6264	6254	6203
(b) Mold Tare	4242	4242	4242	4242
(c) [a-b] Wet Wt.	41.34	4.46	4.44	4.32
(d) Wet Density ( $\rho_w$ ) lb/ft <sup>3</sup>	130.82	133.8	133.2	129.6
Dry Density ( $\rho_d$ ) lb/ft <sup>3</sup>	115.86	116.8	114.5	109.1

\* A constant factor. Use 30.00 for AASHTO T 99 and 13.33 for AASHTO T 180.

Moisture Determination

Pan No.	C	G	E	C
(r) Wet Soil Wt. + Tare	550.5	407.6	400.8	458.6
(s) Dry Soil Wt. + Tare	508.0	374.7	366.2	410.8
(t) Container Tare Wt.	171.0	149.3	154.2	155.9
(u) Dry Soil Wt. [s-t]	337.0	225.4	212.0	254.9
(v) Water Wt. [r-s]	42.5	32.9	34.6	47.8
(w) % Moisture ( $\frac{v}{u} \times 100$ )	12.6	14.6	16.3	18.8





U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 502 (1)

Source \_\_\_\_\_

Where sampled \_\_\_\_\_

Quantity represented \_\_\_\_\_

Sample of SOILLot No. \_\_\_\_\_ Sample No. PLI-3

Sampled By: \_\_\_\_\_ Date: \_\_\_\_\_

Tested by Jonathan Daw Date 1/22/97

TEST ---	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
TEST NUMBER ---	1	2	1	2
No. of blows (liquid limit test)	20	28		
Container No.	A1	A4	A10	A12
A Tare weight of container	15.28	15.44	15.54	15.23
B Weight of wet soil and container	32.97	31.14	18.40	18.16
C Weight of dry soil and container	28.30	27.14	17.99	17.71
D Weight of dry soil [C - A]	13.02	11.70	2.45	2.48
E Weight of moisture [B - C]	4.67	4.00	0.41	0.45
F Percent moisture [ $\frac{E}{D}(100)$ ]	35.9	34.2	16.7	18.1

Liquid Limit<sup>1</sup>

35.0 34.7

Plastic Limit<sup>2</sup> (P)

16.7 18.1

G. LIQUID LIMIT (mean)

35

H. PLASTIC LIMIT (Mean)

17

PLASTIC INDEX (G - H)

18

M. W. Vivier  
Marcel W. Vivier  
EFLHD Materials Engineer


<sup>1</sup> Obtained using nomograph chart. See "Proctor" statement in AASHTO T 88.  
<sup>2</sup> See "Proctor" statement in AASHTO T 88.

% MOISTURE

AS MOULDED	SOAKED	EXPANSION (%)
10 BLOBS	16.2	24.9
25 BLOBS	16.5	70.7
60 BLOBS	16.3	70.4
		0.4

PROJECT: SPIL SOZ(1)  
 SAMPLE NO: PLG-3  
 LAB NO: E-96-0432

~~ALL D. N. WATER~~  
 INTEREST N. WATER  
 FILLING MATERIALS EQUIPMENT



PENETRATION (INCHES)

NOTES: 1. ALL TESTS WERE RUN AT 100°F. 2. ALL TESTS WERE RUN AT 100°F. 3. ALL TESTS WERE RUN AT 100°F.

E-96-0433

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATIONRequest for and Report of  
SOIL CLASSIFICATION TESTPROJECT SHIL 502(1) SAMPLE NO. VC-6

SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_

MATERIAL TO BE USED FOR \_\_\_\_\_

SAMPLED BY \_\_\_\_\_ FROM Depth 0-2.1 DATE 8/29/96

PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB \_\_\_\_\_

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	1/28	E-96-0433	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	1/29	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	1/30	"	48	/
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	1/30	"	19	/
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	1/30	"	29	/
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	2/18/97	"	A-7.6(22)	/
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99 C	1/23	E-96-0433	Density: 113.9 Moisture: 16.3	/
<input checked="" type="checkbox"/> OTHER	T 193		"	CBR 5.9	/

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project records

*M. W. Vivier*  
 Marcel W. Vivier  
 Field Materials Engineer

Reported by: *Nathaniel J. Danes*

Name

2/18/97

Date



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

E-96-0433

# Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 502(1)

Source: \_\_\_\_\_

Where Sampled: Depth 0-2.1

Quantity Represented: \_\_\_\_\_

Sample Of: SOIL

Lot No.: \_\_\_\_\_ Sample No.: VC-6

Sampled By: \_\_\_\_\_ Date: 8/29/96

Tested By: Patricia Jan Date: 1/23/97

Method: T 99C Max. Dry Density: 113.9

Optimum Moisture: 16.3 Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	1	2	3	4
(a) Wet Soil + Tare	6114	6202	6248	6232
(b) Mold Tare	4242	4242	4242	4242
(c) [a-b] Wet Wt.	413	432	448	439
(d) Wet Density ( $\gamma_w$ ) lb/ft <sup>3</sup>	123.9	124.6	132.6	131.7
Dry Density ( $\gamma_d$ ) lb/ft <sup>3</sup>	109.8	112.7	113.8	111.0

\* A constant factor. Use 30.00 for AASHTO T 99 and 13.33 for AASHTO T 180.

Moisture Determination

Pan No.	C	16	1E	1C
(r) Wet Soil Wt. + Tare	571.0	486.6	450.4	397.3
(s) Dry Soil Wt. + Tare	523.5	442.6	408.4	359.2
(t) Container Tare Wt.	171.1	149.2	154.1	155.9
(u) Dry Soil Wt. [s-t]	352.4	293.4	254.3	203.3
(v) Water Wt. [r-s]	47.5	44.0	42.0	38.1
(w) % Moisture [ $\frac{v}{u} \cdot 100$ ]	13.5	15.0	16.5	18.7





E-96-0433



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 502(1)

Source \_\_\_\_\_

Where sampled Depth 0-2.1

Quantity represented \_\_\_\_\_

Sample of soilLot No. \_\_\_\_\_ Sample No. VC-6Sampled By: \_\_\_\_\_ Date: 8/29/96Tested by Michael J. Dan Date 1/30/97

TEST - - -	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
TEST NUMBER - - -	1	2	1	2
No. of blows (liquid limit test)	<u>25</u>	<u>26</u>		
Container No.	<u>A3</u>	<u>A4</u>	<u>A12</u>	<u>A13</u>
A Tare weight of container	<u>15.69</u>	<u>15.42</u>	<u>15.23</u>	<u>15.73</u>
B Weight of wet soil and container	<u>34.35</u>	<u>32.25</u>	<u>19.25</u>	<u>20.14</u>
C Weight of dry soil and container	<u>28.30</u>	<u>26.83</u>	<u>18.60</u>	<u>19.43</u>
D Weight of dry soil (C - A)	<u>12.61</u>	<u>11.41</u>	<u>3.37</u>	<u>3.70</u>
E Weight of moisture (B - C)	<u>6.05</u>	<u>5.42</u>	<u>0.65</u>	<u>0.71</u>
F Percent moisture ( $\frac{E}{D}(100)$ )	<u>48.0</u>	<u>47.5</u>	<u>19.3</u>	<u>19.2</u>

Liquid Limit<sup>1</sup>48.048.0Plastic Limit<sup>2</sup> (P)19.319.2

G. LIQUID LIMIT (mean)

48.0

H. PLASTIC LIMIT (Mean)

19

PLASTIC INDEX (G - H)

29

<sup>1</sup> Obtained using semi-graph chart. See "Precision" statement in AASHTO T 89.  
<sup>2</sup> See "Precision" statement in AASHTO T 90.


M. W. Vivier  
Materials Engineer

% MOISTURE  
AS MOULDED SOAKED Expansion (%)

10 BLOBS	17.1	26.5	3.6
25 BLOBS	16.9	23.2	6.8
60 BLOBS	17.5	20.0	1.1

PROJECT: SHIL SOLID  
SAMPLE NO.: VC-6  
LAB NO: E-96-DA33

Mr. W. Vivian  
Materials Engineer



95 100 105 110 115  
DRY DENSITY AS MOULDED (pcf)

95% MAXIMUM DENSITY  
= 113.9 pcf = 108.7 pcf

CBR @ 0.1 = 5.9  
CBR @ 0.2 = 4.5

CBR = 5.9

PENETRATION (INCHES)

E-96-0434

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATIONRequest for and Report of  
SOIL CLASSIFICATION TESTPROJECT SHIL 502(1) SAMPLE NO. R-2

SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_

MATERIAL TO BE USED FOR \_\_\_\_\_

SAMPLED BY \_\_\_\_\_ FROM \_\_\_\_\_ DATE 8/29/96

PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB \_\_\_\_\_

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	<u>2/24/97</u> <u>78</u>	E-96-0434	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	<u>2/25</u> <u>78</u>	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	<u>2/24</u> <u>78</u>	"	50	/
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	<u>2/24</u> <u>78</u>	"	24	/
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	<u>2/24</u> <u>78</u>	"	26	/
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	<u>3/3/97</u> <u>78</u>	"	A-7-6(7)	/
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99C	<u>2/24</u> <u>78</u>	E-96-0434	Max. Density: 117.6 Opt. Moist: 13.8	/
<input checked="" type="checkbox"/> OTHER	T 193	<u>78</u>	"	CBR 7.5	/

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project recordsM. W. Vivier  
Marcel W. Vivier  
TLHD Materials EngineerReported by: [Signature]  
Name3/4/97

Date



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

# Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 502(1)

Source: \_\_\_\_\_

Where Sampled: \_\_\_\_\_

Quantity Represented: \_\_\_\_\_

Sample Of: SOIL

Lot No.: \_\_\_\_\_

Sample No.: R-2

Sampled By: \_\_\_\_\_

Date: 8/29/96Tested By: Johnnie DavisDate: 2/24/97Method: T 99 CMax. Dry Density: 117.6Optimum Moisture: 13.8

Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	1	2	3	4
(a) Wet Soil + Tare	6176	6268	6269	6214
(b) Mold Tare	4242	4242	4242	4242
(c) [a-b] Wet Wt.	4.26	4.47	4.47	4.35
(d) Wet Density ( $\rho_w$ ) lb/ft <sup>3</sup>	127.8	134.1	134.1	130.5
Dry Density [ $\frac{c}{1+w}$ ] lb/ft <sup>3</sup>	114.43	117.5	115.7	110.4

\* A constant factor. Use 30.00 for AASHTO T 99 and 13.33 for AASHTO T 180.

Moisture Determination

Pan No.	1E	C	1G	1C
(r) Wet Soil Wt. + Tare	671.9	577.0	515.7	617.5
(s) Dry Soil Wt. + Tare	617.3	526.9	465.3	546.3
(t) Container Tare Wt.	154.8	171.2	149.1	155.9
(u) Dry Soil Wt. [s-t]	463.1	355.7	316.2	390.4
(v) Water Wt. [r-s]	54.6	50.1	50.4	71.2
(w) % Moisture [ $\frac{v}{u} \times 100$ ]	11.8	14.1	15.9	18.2





U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

# WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 502(1)

Source \_\_\_\_\_

Where sampled \_\_\_\_\_

Quantity represented \_\_\_\_\_

Sample of SOILLot No. \_\_\_\_\_ Sample No. R-2Sampled By: \_\_\_\_\_ Date: 8/29/96Tested by Jeffrey L. Davis Date 2/24/97

TEST - - -	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
	1	2	1	2
TEST NUMBER - - -				
No. of blows (liquid limit test)	<u>20</u>	<u>22</u>		
Container No.	<u>A1</u>	<u>A10</u>	<u>A6</u>	<u>A12</u>
A Tare weight of container	<u>15.28</u>	<u>15.55</u>	<u>15.43</u>	<u>15.24</u>
B Weight of wet soil and container	<u>33.35</u>	<u>33.21</u>	<u>18.87</u>	<u>19.09</u>
C Weight of dry soil and container	<u>27.22</u>	<u>27.27</u>	<u>18.24</u>	<u>18.31</u>
D Weight of dry soil [C - A]	<u>11.94</u>	<u>11.72</u>	<u>2.81</u>	<u>3.07</u>
E Weight of moisture [B - C]	<u>6.13</u>	<u>5.94</u>	<u>0.63</u>	<u>0.78</u>
F Percent moisture ( $\frac{E}{D}(100)$ )	<u>51.3</u>	<u>50.7</u>	<u>22.4</u>	<u>25.4</u>

Liquid Limit<sup>1</sup>50.0 49.9Plastic Limit<sup>2</sup> (P)22.4 25.4

G. LIQUID LIMIT (mean)

50

H. PLASTIC LIMIT (Mean)

24

PLASTIC INDEX (G - H)

26

<sup>1</sup> Obtained using nomograph chart. See "Precision" statement in AASHTO T 89.  
<sup>2</sup> See "Precision" statement in AASHTO T 90.

*M. W. Vivier*  
Marcel W. Vivier  
LLHD Materials Engineer

AS MOULDED SOAKED EXPANSION (%)


0 10 BLOWS	13.9	22.9	1.7
A 25 BLOWS	14.0	21.0	1.7
B 60 BLOWS	14.2	19.2	1.4

PROJECT: SHIL 502(1)

SAMPLE NO: P-2

LAB NO: E-96-0134

MM of 1/2 inch  
LTD Materials Engineering  
LTD Construction Engineering



DRY DENSITY AS MOULDED

95% OF MAXIMUM DENSITY  
= 95 (117.6 PCF) = 111.7 PCF

CBR @ 0.1 = 7.0

CBR @ 0.2 = 7.5

CBR = 7.5

CBR @ 0.2 = 11.9

CBR @ 0.1 = 13.6

CBR @ 0.1 = 5.0

CBR @ 0.1 = 1.2

CBR @ 0.2 = 1.7

PENETRATION (INCHES)

E-96-0435

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATIONRequest for and Report of  
SOIL CLASSIFICATION TESTPROJECT SHIL 502(1) SAMPLE NO. RS-3

SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_

MATERIAL TO BE USED FOR \_\_\_\_\_

SAMPLED BY \_\_\_\_\_ FROM Depth: 0-1.8 DATE 10/18/96PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB 12/26/97

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	1/16	E-96-0435	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	1/17	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	1/18	"	29	✓
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	1/18	"	18	✓
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	1/18	"	11	✓
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	1/22	"	A-6(8)	✓
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99C	4/18	E-96-0435	Max! Density: 115.3	✓
<input checked="" type="checkbox"/> OTHER	T 193	4/13	"	Moist: 15.8	✓
				CBR 7.8	✓

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project recordsM. W. Vivier  
Marcel W. Vivier  
FIELD Materials EngineerReported by: Nathaniel Damer  
Name1/22/97  
Date



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 502(1)

Source: \_\_\_\_\_

Where Sampled: \_\_\_\_\_

Quantity Represented: \_\_\_\_\_

Sample Of: \_\_\_\_\_

Lot No.: \_\_\_\_\_

Sample No.: R5-3

Sampled By: \_\_\_\_\_

Date: 10/18/96Tested By: NathanielDate: 1/6/97Method: T 99CMax. Dry Density: 115.3Optimum Moisture: 15.8%

Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	A	B	C	D
(a) Wet Soil + Tare	6226	6263	6188	6164
(b) Mold Tare	4242	4242	4242	4242
(c) [a-b] Wet Wt.	4.37	4.46	4.29	4.24
(d) Wet Density (*)c lb/ft <sup>3</sup>	131.1	133.8	128.7	127.2
Dry Density [ $\frac{c}{1+w}$ ]	114.5	115.3	108.5	108.0

\* A constant factor. Use 30.00 for AASHTO T 99 and 19.33 for AASHTO T 180.

Moisture Determination

Pan No.	1G	1E	1C	1A
(r) Wet Soil Wt. + Tare	633.1	767.6	584.5	650.9
(s) Dry Soil Wt. + Tare	571.8	683.0	517.2	567.2
(t) Container Tare Wt.	149.2	154.2	155.9	149.3
(u) Dry Soil Wt. [s-t]	422.6	528.8	361.3	417.9
(v) Water Wt. [r-s]	61.3	84.6	67.3	83.7
(w) % Moisture [ $\frac{v}{u} (100)$ ]	14.5	16.0	18.6	20.0





E-96-0435



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 502(1)

Source \_\_\_\_\_

Where sampled \_\_\_\_\_

Quantity represented \_\_\_\_\_

Sample of \_\_\_\_\_

Lot No. \_\_\_\_\_ Sample No. RS-3Sampled By: \_\_\_\_\_ Date: 10/18/96Tested by Mathew J. [Signature] Date 1/8/97

TEST ---	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
TEST NUMBER ---	1	2	1	2
No. of blows (liquid limit test)	<u>22</u>	<u>30</u>		
Container No.	<u>A4</u>	<u>A1</u>	<u>A10</u>	<u>A11</u>
A Tare weight of container	<u>15.45</u>	<u>15.28</u>	<u>15.54</u>	<u>15.09</u>
B Weight of wet soil and container	<u>30.39</u>	<u>31.94</u>	<u>20.22</u>	<u>19.37</u>
C Weight of dry soil and container	<u>26.97</u>	<u>28.20</u>	<u>19.53</u>	<u>18.70</u>
D Weight of dry soil [C - A]	<u>11.52</u>	<u>12.92</u>	<u>3.99</u>	<u>3.61</u>
E Weight of moisture [B - C]	<u>3.42</u>	<u>3.74</u>	<u>0.69</u>	<u>0.67</u>
F Percent moisture [ $\frac{E}{D}(100)$ ]	<u>29.7</u>	<u>28.9</u>	<u>17.3</u>	<u>18.6</u>

Liquid Limit<sup>1</sup>29.3 / 29.5Plastic Limit<sup>2</sup> [F]17.3 / 18.6

G. LIQUID LIMIT (mean)

29

H. PLASTIC LIMIT (Mean)

18

PLASTIC INDEX [G - H]

11


<sup>1</sup> Obtained using nomograph chart. See "Precision" statement in AASHTO T 89.  
<sup>2</sup> See "Precision" statement in AASHTO T 90.

M. W. Vivier  
Marcel W. Vivier  
LLHD Materials Engineer

AS MOLDED SOAKED EXPANSION (%)

10 BLOBS	16.1	76.8	10.3
25 BLOBS	16.2	20.9	0.5
60 BLOBS	16.1	20.9	0.2

PROJECT: SHIL SOZG  
 SAMPLE NO: RS-3  
 LAB NO: E-96-0435



DRY DENSITY AS MOULDED

95% OF MAXIMUM DENSITY  
 = 95 (15.3 PCF) = 109.5 PCF

CBR @ 0.1 = 7.0

CBR @ 0.2 = 6.6

CBR = 7.0

PENETRATION (INCHES)

E-96-0436

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATIONRequest for and Report of  
SOIL CLASSIFICATION TESTPROJECT SHIL 502(1) SAMPLE NO. T-4

SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_

MATERIAL TO BE USED FOR \_\_\_\_\_

SAMPLED BY \_\_\_\_\_ FROM \_\_\_\_\_ DATE 8/29/96

PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB \_\_\_\_\_

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	2/24 79	E-96-0436	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	2/25 79	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	2/23 79	"	31	/
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	2/23 79	"	18	/
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	2/23 79	"	13	/
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	2/26 79	"	A-7-6(8)	
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99 C	2/17 79	E-96-0436	Max Den: 123.3 % moist: 11.3	/
<input checked="" type="checkbox"/> OTHER	T 193	2/23 79	"	CBR 6.5	/

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project records

*M. W. Vivier*  
 Marcel W. Vivier  
 TND Materials Engineer

Reported by: *Nathaniel D. Davis*

Name

2/26/97

Date



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

E-96-0436

## Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 502(1)

Source: \_\_\_\_\_

Where Sampled: \_\_\_\_\_

Quantity Represented: \_\_\_\_\_

Sample Of: SOIL

Lot No.: \_\_\_\_\_ Sample No.: T-4

Sampled By: \_\_\_\_\_ Date: 8/29/96 Tested By: Patricia J. Dan Date: 2/17/97

Method: T 99 Max. Dry Density: 123.3 Optimum Moisture: 11.3 Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	1	2	3	4
(a) Wet Soil + Tare	6235	6315	6298	6229
(b) Mold Tare	4241	4241	4241	4241
(c) [a-b] Wet Wt.	4.40	4.57	4.53	4.38
(d) Wet Density ( $\rho_w$ ) lb/ft <sup>3</sup>	132.0	137.1	135.9	131.4
Dry Density ( $\rho_d$ ) lb/ft <sup>3</sup>	120.8	123.1	119.6	113.8

\* A constant factor. Use 30.00 for AASHTO T 99 and 13.33 for AASHTO T 180.

Moisture Determination

Pan No.	A	1E	1G	K
(r) Wet Soil Wt. + Tare	638.3	535.6	512.5	542.2
(s) Dry Soil Wt. + Tare	598.7	496.6	469.0	490.3
(t) Container Tare Wt.	173.0	154.3	149.1	155.8
(u) Dry Soil Wt. [s-t]	425.7	342.3	319.9	334.5
(v) Water Wt. [r-s]	39.6	39.0	43.5	51.9
(w) % Moisture [ $\frac{v}{u}(100)$ ]	9.3	11.4	13.6	15.5





U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

## WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 502(1)

Source \_\_\_\_\_

Where sampled \_\_\_\_\_

Quantity represented \_\_\_\_\_

Sample of SoilLot No. \_\_\_\_\_ Sample No. T-4Sampled By: \_\_\_\_\_ Date: 8/29/96Tested by W. Vivier Date 2/23/97

TEST ---	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
TEST NUMBER ---	1	2	1	2
No. of blows (liquid limit test)	20	23		
Container No.	A4	A11	A6	A1
A Tare weight of container	15.42	15.09	15.42	15.28
B Weight of wet soil and container	38.55	38.19	20.89	19.39
C Weight of dry soil and container	33.01	32.73	19.54	18.75
D Weight of dry soil [C - A]	17.59	17.64	4.12	3.47
E Weight of moisture [B - C]	5.54	5.46	0.75	0.64
F Percent moisture [ $\frac{E}{D}(100)$ ]	31.5	31.0	18.2	18.4
Liquid Limit <sup>1</sup>		30.7	30.7	

Plastic Limit<sup>2</sup> [F]

18.2 18.4

G. LIQUID LIMIT (mean)

31

H. PLASTIC LIMIT (Mean)

18

PLASTIC INDEX (G - H)

13

<sup>1</sup> Obtained using nomograph chart. See "Procedure" statement in AASHTO T 89.  
<sup>2</sup> See "Procedure" statement in AASHTO T 90.

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

*M. de V. Silva*  
 Chief W. Engineer  
 Civil Materials Engineer

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436


PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436

PROJECT: SHILSOA(1)  
 SAMPLE: T-4  
 LAB. No.: E-96-0436



CBR = 6.5

PENETRATION (INCHES)

APPROX. DENSITY IN THE  
 100% REL. HUMIDITY

E-96-0437

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATIONRequest for and Report of  
SOIL CLASSIFICATION TEST

PROJECT SHIL 500 (1) SAMPLE NO. BL-3

SOURCE \_\_\_\_\_ PAY ITEM NO. \_\_\_\_\_

MATERIAL TO BE USED FOR \_\_\_\_\_

SAMPLED BY \_\_\_\_\_ FROM \_\_\_\_\_ DATE 8/29/96

PERSON AUTHORIZING TEST \_\_\_\_\_ DATE SHIPPED TO LAB \_\_\_\_\_

INDICATE EACH TEST TO BE RUN	TEST NO.	TESTED BY/DATE	LAB NO.	TEST RESULTS	SPECIFICATION
<input checked="" type="checkbox"/> AMOUNT FINER THAN 0.075 mm	T 11	2/17/97 78	E-96-0437	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> SIEVE ANALYSIS	T 27	2/18 78	"	TO BE LISTED ON THE REVERSE SIDE	"
<input checked="" type="checkbox"/> LIQUID LIMIT	T 89	2/18 78	"	25	✓
<input checked="" type="checkbox"/> PLASTIC LIMIT	T 90	2/18 78	"	19	✓
<input checked="" type="checkbox"/> PLASTIC INDEX	T 90	2/18 78	"	6	✓
<input checked="" type="checkbox"/> CLASSIFICATION	T 317	2/24 78	"	A-4(1)	✓
<input type="checkbox"/> PARTICLE SIZE BY HYDROMETER	T 88				
<input checked="" type="checkbox"/> OTHER	T 99 C	2/19 78	E-96-0437	Max. Den. 12.4 opt. Moist. 10.7	✓
<input checked="" type="checkbox"/> OTHER		2/20 78	"	CBR 10.7	✓

REMARKS: Forward original copy to Regional Lab  
Forward one copy with sample  
Retain one copy in Project records

*m. W. Vivier*  
M. W. Vivier  
Materials Engineer

Reported by:

*Nathan D. Davis*  
Nathan D. Davis

2/24/97

Date



U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

E-96-0437

# Worksheet for Determining Moisture/Density Relationships AASHTO T 99 AND AASHTO T 180

Project: SHIL 500(1)

Source: \_\_\_\_\_

Where Sampled: \_\_\_\_\_

Quantity Represented: \_\_\_\_\_

Sample Of: SOIL

Lot No.: \_\_\_\_\_ Sample No.: BL-3

Sampled By: \_\_\_\_\_ Date: 8/29/96

Tested By: Johnnie Sam Date: 1/29/97

Method: T 99 C Max. Dry Density: 121.4

Optimum Moisture: 10.7 Specific Gravity: \_\_\_\_\_


Density Determination

Test No.	A	B	C	D
(a) Wet Soil + Tare	6249	6281	6263	6217
(b) Mold Tare	4242	4242	4242	4242
(c) [a-b] Wet Wt.	4.42	4.50	4.46	4.35
(d) Wet Density (*)c lb/ft <sup>3</sup>	132.6	135.0	133.8	130.5
Dry Density [ $\frac{c}{1+w}$ ]	120.9	121.1	118.0	112.7

\* A constant factor. Use 30.00 for AASHTO T 99 and 13.33 for AASHTO T 180.

Moisture Determination

Pan No.	C	A	B	E
(r) Wet Soil Wt. + Tare	608.4	553.9	623.6	657.1
(s) Dry Soil Wt. + Tare	569.8	519.7	575.1	576.9
(t) Container Tare Wt.	171.1	221.4	213.6	208.5
(u) Dry Soil Wt. [s-t]	398.7	298.3	361.5	387.4
(v) Water Wt. [r-s]	38.6	34.2	48.5	61.2
(w) % Moisture [ $\frac{v}{u} \times 100$ ]	9.7	11.5	13.4	15.8







U.S. Department of Transportation  
Federal Highway Administration  
Federal Lands Highway Office

# WORKSHEET FOR LIQUID LIMIT AND PLASTIC LIMIT OF SOILS AASHTO T 89 AND AASHTO T 90

Project SHIL 500C1

Source \_\_\_\_\_

Where sampled \_\_\_\_\_

Quantity represented \_\_\_\_\_

Sample of SOIL

Lot No. \_\_\_\_\_ Sample No. BL-3

Sampled By: \_\_\_\_\_ Date: 8/29/96

Tested by Patricia J. [Signature] Date 2/18/97

TEST - - -	LIQUID LIMIT (%)		PLASTIC LIMIT (%)	
TEST NUMBER - - -	1	2	1	2
No. of blows (liquid limit test)	27	30		
Container No.	A1	A10	A13	A4
A Tare weight of container	15.30	15.54	15.74	15.42
B Weight of wet soil and container	39.29	37.09	20.37	20.11
C Weight of dry soil and container	34.53	32.82	19.58	19.41
D Weight of dry soil [C - A]	19.23	17.28	3.84	3.99
E Weight of moisture [B - C]	4.76	4.27	0.79	0.70
F Percent moisture [ $\frac{E}{D}(100)$ ]	24.8	24.7	20.6	17.5

Liquid Limit<sup>1</sup>

25.0 / 25.2

Plastic Limit<sup>2</sup> (P)

20.6 / 17.5

G. LIQUID LIMIT (mean)

25

H. PLASTIC LIMIT (Mean)

19

PLASTIC INDEX (G - H)


6

<sup>1</sup> Obtained using nomograph chart. See "Precision" statement in AASHTO T 89.  
<sup>2</sup> See "Precision" statement in AASHTO T 90.

PROJECT: PHIL 30000  
SAMPLE NO. 8L-3

LAB NO. E-96-0237

*W. A. N. N. N.*  
MARCEL W. NINIST  
FIELD MATERIALS ENGINEER



PENETRATION (INCHES)

AVENUE 100, BIRMINGHAM, ALA. 35202  
PHONE 251-2111

## **APPENDIX E - Boring Summary**

**TABLE E-1 SUMMARY OF PAVEMENT BORINGS  
PITTSBURG LANDING ROAD I**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
PLI-1	90	40	A-6 (11)
PLI-2	90	90	Silty Clay
PLI-3	110	120	Clay
PLI-4	90	120	Sandy Clay
PLI-5	90	120	A-6 (3)
PLI-6	90	120	
PLI-7	70	120	
PLI-8	90	70	
PLI-9	--	--	Silty Clay
PLI-10	--	--	A-6 (12)
PLI-11	--	--	A-6 (13)
PLI-12	110	70	

**TABLE E-2 SUMMARY OF PAVEMENT BORINGS  
PITTSBURG LANDING ROAD II**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
PLII-1	90	70	A-6 (11)
PLII-2	70	120	Clay
PLII-3	?	?	A-2-4 (0)

**TABLE E-3 SUMMARY OF PAVEMENT BORINGS  
ENTRANCE ROAD**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
E-1	30	130	A-6 (16)
E-2	40	40	A-7-6 (17)

**TABLE E-4 SUMMARY OF PAVEMENT BORINGS  
SERVICE ROAD**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
S-1	90	100	A-7-6 (25)

**TABLE E-5 SUMMARY OF PAVEMENT BORINGS  
VISITOR CENTER PARKING**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
VC-1	100	140	A-6 (13)
VC-2	80	220	Clay
VC-3	90	90	A-6 (9)
VC-4	70	150	Silty Clay
VC-5	100	110	A-6 (18)
VC-6	130	80	Clay

**TABLE E-6 SUMMARY OF PAVEMENT BORINGS  
CORINTH-PITTSBURG LANDING ROAD**

<b>Boring</b>	<b>Concrete Thickness (mm)</b>	<b>AC Thickness (mm)</b>	<b>Subgrade</b>
CP-1	160	--	A-6 (13)
CP-2	130	--	Silty Clay
CP-3	160	--	A-6 (10)
CP-4	130	--	Silty Clay
CP-5	130	--	A-6 (13)
CP-6	120	--	Silty Clay
CP-7	120	70	A-4 (0)
CP-8	150	30	A-2-4 (0)
CP-9	130	90	A-4 (0)
CP-10	130	--	A-6 (14)
CP-11	130	--	A-6 (1)

Boring	Concrete Thickness (mm)	AC Thickness (mm)	Subgrade
CP-12	120	--	Silty Clay

**TABLE E-7 SUMMARY OF PAVEMENT BORINGS  
MCCLERNAND ROAD**

Boring	AC Thickness (mm)	Aggregate Base Thickness (mm)	Subgrade
MS-1	80	None	A-6 (13)
MS-2	80	None	Silty Clay
MS-3	30	None	A-6 (17)
MS-4	None	None	A-6 (17)
MS-5	100	None	Silty Clay

**TABLE E-8 SUMMARY OF PAVEMENT BORINGS  
RECONNOITERING ROAD**

Boring	AC Thickness (mm)	Aggregate Base Thickness (mm)	Subgrade
R-1	80	70	A-7-6 (18)
R-2	?	?	Silty Clay
R-3	80	60	A-7-6 (23)

**TABLE E-9 SUMMARY OF PAVEMENT BORINGS  
RHEA SPRINGS ROAD**

Boring	AC Thickness (mm)	Aggregate Base Thickness (mm)	Subgrade
RS-1	80	None	A-6 (4)
RS-2	120	None	A-7-6 (20)
RS-3	--	None	Silty Clay
RS-4	130	140	
RS-5	160	140	
RS-6	70	None	

**TABLE E-10 SUMMARY OF PAVEMENT BORINGS  
EASTERN CORINTH ROAD**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
EC-1	110	140	A-6 (15)
EC-2	90	100	Silty Clay
EC-3	100	130	A-7-6 (16)

**TABLE E-11 SUMMARY OF PAVEMENT BORINGS  
TH PARKING**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
T-1	90	None	
T-2	90	None	
T-3	--	--	A-6 (15)
T-4	--	--	Silty Clay

**TABLE E-12 SUMMARY OF PAVEMENT BORINGS  
HAMBURG-SAVANNAH ROADS**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
J-1	--	--	A-4 (0)
J-2	90	None	
J-3	70	None	

**TABLE -13 SUMMARY OF PAVEMENT BORINGS  
PEACH ORCHARD PARKING LOT**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
PO-1	70	None	A-6 (17)
PO-2	60	None	Silty Clay

**TABLE E-14 SUMMARY OF PAVEMENT BORINGS  
BLOODY POND TOUR STOP**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
BP-1	90	None	A-4 (1)
BP-2	60	None	A-6 (7)

**TABLE E-15 SUMMARY OF PAVEMENT BORINGS  
BROWN'S LANDING ROAD**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
BL-1	--	--	A-2-4 (0)
BL-2	--	--	A-6 (9)
BL-3	--	--	Silty Clay
BL-4	--	--	A-6 (11)
BL-5	--	--	A-6 (15)

**TABLE X-16 SUMMARY OF PAVEMENT BORINGS  
VISTA**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
V-1	--	--	A-4(1)

**TABLE X-17 SUMMARY OF PAVEMENT BORINGS  
HAMBURG-SAVANNAH ROAD**

<b>Boring</b>	<b>AC Thickness (mm)</b>	<b>Aggregate Base Thickness (mm)</b>	<b>Subgrade</b>
HS-1	60	None	Silty Clay
HS-2	80	None	Clay
HS-3	70	None	Silty Clay
HS-4	90	None	Silty Clay



## **APPENDIX F - RPCC Pavement Condition Survey**

**TABLE 1 - RPCC PAVEMENT CONDITION SURVEY RESULTS  
AND RECOMMENDATIONS  
CORINTH - PITTSBURG ROAD**

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
L1	2M		L45	1H	
L3	1H, 3L		L46	2H	Fix 2' at 45/46 on 46 side
L4	1L, 3L		L48		Exposed reinforcement near 48/49
L5	1M		L50	1H	
L7	1H	+ Blow out	L54	1H	
L8	1M		L56/57		Corner crack & spalling 2'
L9	1H		L57	1M	
L10	1H	+ a pothole	L60	1H	
L12	1H	+ 2 potholes	L65	1H	
L14	2H	At the corner	L66	1H	
L19	1H	+ potholes & 3M	L73	2H	Fix 1.5' at 73/74 on 73 side
L19/20, R19/20	2H	Fix 4' either side of joint.	L74	1H	
L21, R21	2H	Fix 2' at edge 20/21 either side of joint	L75	1H	2 cracks
L21/L22	3M	Fix 3' either side.	L76	1H	
L22/L23	3M, 3L	Fix 6' either side.	L77	1H	
L23/L24	3M, 3L	Fix 3' either side.	L84	1H	
L27	1H	w/ spall at end of crack.	L85	2H	Fix 1.0' at 85/86 on 85 side
L30/L31	2H	Fix 2' either side.	L90	1H	L91 ramp to H-S Rd.
L31	1H		L93	1H	
L32	1H		L95	1H	
L33	1M	+ corner crack & spalling, fix 2' at 33/34 on 33 side	L97	1H	L98 H-S Rd.
L35	1M		L99	2H	Fix 1.0' at 99/100 on 99 side
L37	1H		L104	1/2H	Fix 1.0' at 104/105 on 104 side
L38	1M	At new entrance road.	L106	1H	
L39	3L		L107	1H	Several patches
L40	1L	+ 3L	L111	1H	

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
L43	1H		L113	1H	
L115	1H		L218	1H	
L120	1H		L221	1H	
L121	1L		L223	1H	
L132	1H		L229	1H	At McClelland Rd.
L133	1L	Fix 1.5' at 133/134 on 133 side	L233	1M	
L134a	1H	UDC Monument-turnaround - Replace entire UDC turnaround	L238	1M	
L135a	Potholes	UDC Monument-turnaround	L242	1H	
L134/135, R134/135	2H	Fix 3' either side joint	L243	1,3H	Replace the half on L242 side
L136a	1M	UDC Monument-turnaround	L244	1H	
L142	1H		L247	2H	Fix 2' at 246/247 on 247 side
L146	1H		L254	2H	Fix 1' at 254/255 on 254 side
L147		E-C Rd.	L261	1H	
L158	1H		L263	1H	
L165	1H		L269	1H	At H-P Rd.
L168	1H		L271	1H	
L179	1M		L272	1H	
L185	1M		L273	1H,2M	
L185/186 R185/186	2H	Fix 2.5' either side joint.	L275	1H	
L190 L189/190	1H 2H	Fix 1.5' at 189/190 on 190 side	L286	1H	
L192	1H		L292	1M	
L201	1H		L296	1H	
L205	1H		L315	1H	
L209	1H		L317	2H	Fix 2' at 316/317 on 317 side
L211	1H		L324	1H	

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
L214	Pothole	0.25'dia. at center of slab	L327	1H	
L329/330	H joint spalling	Fix 2' on either side	L360	1H	
L330/329	H joint spalling	Fix 2' on either side	L361	1H	
b/w L333 to 337 are 2 box culverts w/ AC o/L (reconstruct this section).			L362	1H	
L338	1H		L363	1H	
L340	1H		L365	1M	
L340/341	H joint spalling	Fix 2' on either side	L375	1H	
L344/345	H joint spalling	Fix 2' on either side	L377	1H	
L349	1H		L381	1H	
L350	1H		L384	1H	
L351/352	H joint spalling	Fix 2' on either side	L387	1M	
L352	1M		L396	1H	
L354	1H	3 transverse cracks	L403	1H	
L355	1H	several transverse cracks	L405	1H	
L356	1H	2 transverse cracks			
L357/358	L patch				

**TABLE 1 - RPCC PAVEMENT CONDITION SURVEY RESULTS  
AND RECOMMENDATIONS  
CORINTH - PITTSBURG ROAD**

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
R419	1H		R376/375	2H	Fix 2' each side
R413/412	H joint	Fix joint 2' each side	R373/372	2H	Fix 2' each side
R412/411	H joint	Fix joint 2' each side	R372	1H	
R410/409	H joint	Fix joint 2' each side	R372/371	2M	Fix 1' each side
R409/408	2H	Fix joint 2' each side	R371/370	2M	Fix 2' each side
R407/406	2H	Fix joint 1' on 407 side	R370/369	2M	Fix 1' each side
R404/403	2H	Fix joint 1' each side	R369/368	2M	Fix 1' each side
R403/402	2H	Fix 2' each side	R368	1H	
R402	1H		R368/367	2M	Fix 1' each side
R402/401	2H	Fix joint 2' each side	R367/366	2M	Fix 3' each side
R401/400	2H	Fix joint 2' each side	R365/364	2M	Fix 2' each side
R400	1H		R364	1H	
R398/397	2H	Fix 1' each side	R363/362	2M	Fix 2' each side
R397	1,3L		R361	1H	
R396	1M		R356	1H	
R396/395	2M	Fix 2' each side	R354	1H	Fix 2' at 354/353 on 354 side
R395/394	Bad Joint	Fix 2' each side	R352/351	2M	Fix 2' on 352 side
R394	1L		R350	1M	
R393	1H		R345	1H	
R392/391	Bad Joint	Fix 1' each side	R345/344	2H	Fix 2' on each side
R390/389	Bad Joint	Fix 1' each side	R344/343	2H	Fix 2' on each side
R387	1H		R343/342	2H	Fix 1' on each side
R384	1H		R342	1H	
R383	1M		R341	1H	
R381/380	Bad Joint	Fix 1' each side	R341/340	Bad Joint	Fix 1' on each side
R380/379	Bad Joint	Fix 2' each side	R340	1H	
R376	1H		R338	1H	

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
b/w R333 to R337 are two box culverts w/ AC o/L (reconstruct this section)					
R330/329	joint spalling	Fix 2' each side			
R329/328	2H	Fix 3' at 328 side			
R327	1H				
R324	1H				
R323/322	2H	Fix 2' each side			
R322	1H				
R321/320	2H	Fix 2' on 321 side			
R319	1H				
R317	1H		Gore area adjacent to R265/264	1H	
R315	1H		R262	1H	
R309	1H		R259	1H	
R307	1H		R257	1M	
R302	1H		R253	1H	Extra slabs on rt.
R296	1H		R237	1H	
R292	1H		R228	1H	
R286	1H		R224	1H	At McClelland Rd.
R280	1H		R221	1H	
R275	1H		R218	1H	
R272	1H		R215	1H	
R271	1H		R213	1H	
R269	1H				
R268	1H				
R266	1H				
R265	1H				
R263	1H				
R261	1H				

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments
R206	1M		R92	1H	
R196	1H	Extra slabs on rt.	R88	1H	
R184	1H		R87	1H	
R180/179	2M	Fix 2' each side	R83	1H	
R178	1M		R81	1H	
R178/177	2M	Fix 2' each side	R78	1H	
R176/175	2M	Fix 3' each side	R77	1H	
R170	1H		R68	1H	
R167	1H		R62	1H	
R162	1H		R57	1H	
R160/159	2H	Fix 4' each side	R52	1H	
R159	1H	At culvert	R45	1H	
R152	1M		R39/38	Bad Joint	Fix 2' each side
R148	1H		R37/36	2M	Fix 2' each side
R142	1H		R34	1H	
R141/140	2M	Fix 2' each side	R32	1H	
R140	1H		R27	1H	
R140/139	2M	Fix 2' each side	R22	1H	
R139/138	2M	Fix 2' each side	R19	1H	
R136/135	2M	Fix 2' each side	R13	1H	
R131/130	2M	Fix 2' each side	R12/11	Bad Joint	Fix 2' each side
R128/127	2H	Fix 2' each side	R11/10	2M	Fix 2' each side
Reconstruct AC pull-off on opp. side of road from UDC monument.			R10	1H	
R127/126	2M	Fix 2' each side	R10/9	2M	Fix 2' each side
R124	1H		R2	1H	
R122	1H		<b>Defect Legend</b> 1 = transverse crack near mid-slab 2 = corner break 3 = longitudinal cracks along dowels  L = Low severity M = Medium severity H = High severity		
R119	1H,2M				
R108	1H				
R104	1H				
R99	1H,2M				
R97/96	2M	Fix 2' each side			
R96/95	2M	Fix 2' each side			

Replace Slab	Defects	Comments	Replace Slab	Defects	Comments



## **APPENDIX G - Pavement Design**

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Flexible Structural Design Module

Brown's Road Widening and parking area

CBR = 7

### Flexible Structural Design

80-kN ESALs Over Initial Performance Period	26,331
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Roadbed Soil Resilient Modulus	72,398 kPa
Stage Construction	1
Calculated Design Structural Number	41 mm

### Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	284
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %
Percent Trucks in Design Direction	50 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	497
2	1	2	1.75	0	22,053
3	0.5	2	0.6	0	3,781
Total	100	-	-	-	26,331

Growth Compound

Total Calculated Cumulative ESALs 26,331

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Surface Course	0.44	1	40	7.35	18
2	HACP Base Course	0.4	1	60	7.35	24

<u>Layer</u>	<u>Material Description</u>	Struct Coef. <u>(Ai)</u>	Drain Coef. <u>(Mi)</u>	Thickness <u>(Di)(mm)</u>	Width <u>(m)</u>	Calculated <u>SN (mm)</u>
3	Aggregate Base Course	0.14	1	200	7.35	28
Total	-	-	-	300	-	70

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Overlay Design Module

Pittsburg Landing Road I and Visitor Center/Cementery Parking Areas

### AC Overlay of AC Pavement

Structural Number for Future Traffic	44 mm	
<u>Design Method</u>	<u>Effective Existing</u>	<u>Overlay</u>
Component Analysis	<u>Structural Number (mm)</u>	<u>Structural Number (mm)</u>
Remaining Life	35	9
Non-Destructive Testing	-	-
	-	-

### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	41,165
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	72,389 kPa

Calculated Structural Number for Future Traffic      44 mm

### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural</u> <u>Coefficient</u>	<u>Drainage</u> <u>Coefficient</u>	<u>Thickness</u> <u>(mm)</u>
1	HACP Surface Course	0.25	1	90
2	Aggregate Base Course	0.1	1	120
Milling Thickness		0 mm		

#### Calculated Results\*

Calculated Pavement Structural Number Before Milling	35 mm
Calculated Effective Pavement Structural Number	35 mm

\*Note: This value is not represented by the inputs or an error occurred in calculation.

### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	444

Number of Lanes in Design Direction 1  
 Percent of All Trucks in Design Lane 100 %  
 Percent Trucks in Design Direction 50 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	776
2	1	2	1.75	0	34,478
3	0.5	2	0.6	0	5,910
Total	100	-	-	-	41,165

Growth Compound

Total Calculated Cumulative ESALs 41,165

### Structural Number for New Existing Pavement

Layer	Material Description	Structural Coefficient	Drainage Coefficient	Thickness (mm)
1	AC Surface	0.25	1	90
2	Granular Base	0.1	1	120

Milling Thickness 0 mm

#### Calculated Results

Calculated New Structural Number Before Milling 35 mm  
 Calculated New Structural Number 35 mm

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Overlay Design Module

Visitor Center  
Use ADT from Pittsburg landing Rd II  
CBR = 6

### AC Overlay of AC Pavement

Structural Number for Future Traffic

16 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	32	0
Remaining Life	-	-
Non-Destructive Testing	-	-

### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	228
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	62,055 kPa

Calculated Structural Number for Future Traffic 16 mm

### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.2	1	95
2	Aggregate Base Course	0.1	1	130

Milling Thickness 0 mm

#### Calculated Results\*

Calculated Pavement Structural Number Before Milling	32 mm
Calculated Effective Pavement Structural Number	32 mm

\*Note: This value is not represented by the inputs or an error occurred in calculation.

### Future Rigorous ESAL Calculation

Performance Period (years)

Two-Way Traffic (ADT) -  
 Number of Lanes in Design Direction -  
 Percent of All Trucks in Design Lane - %  
 Percent Trucks in Design Direction - %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/ Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
Total	-	-	-	-	-
Growth			Simple		
Total Calculated Cumulative ESALs			- *		

\*Note: This value is not represented by the inputs or an error occurred in calculation.

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
I	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

### A Proprietary AASHTOWare Computer Software Product

#### Overlay Design Module

Entrance road - AC Overlay  
Using same ADT as Pittsburg landing Road I

#### AC Overlay of AC Pavement

Structural Number for Future Traffic

44 mm

Design Method  
Component Analysis  
Remaining Life  
Non-Destructive Testing

Effective Existing  
Structural Number (mm)

17

Overlay  
Structural Number (mm)

27

-

-

#### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period 41,165  
Initial Serviceability 4.2  
Terminal Serviceability 2.2  
Reliability Level 85 %  
Overall Standard Deviation 0.49  
Subgrade Resilient Modulus 72,398 kPa

Calculated Structural Number for Future Traffic

44 mm

#### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	35
2	Aggregate Base Course	0.1	1	85

Milling Thickness

0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling 17 mm  
Calculated Effective Pavement Structural Number 17 mm

#### Future Rigorous ESAL Calculation

Performance Period (years) 20  
Two-Way Traffic (ADT) 444  
Number of Lanes in Design Direction 1  
Percent of All Trucks in Design Lane 100 %



Percent Trucks in Design Direction

50 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	776
2	1	2	1.75	0	34,478
3	0.5	2	0.6	0	5,910
Total	100	-	-	-	41,165

Growth

Compound

Total Calculated Cumulative ESALs

41,165

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	62	-	27
Total	-	-	-	62	-	27

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Overlay Design Module

Brown's Landing Road  
CBR = 7

### AC Overlay of AC Pavement

Structural Number for Future Traffic

41 mm

Design Method  
Component Analysis  
Remaining Life  
Non-Destructive Testing

Effective Existing  
Structural Number (mm)

23

Overlay  
Structural Number (mm)

18

-

-

-

-

### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	26,145
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	72,398 kPa

Calculated Structural Number for Future Traffic 41 mm

### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	90

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	23 mm
Calculated Effective Pavement Structural Number	23 mm

### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	282
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %
Percent Trucks in Design Direction	50 %

<u>Vehicle Class</u>	<u>Percent of ADT</u>	<u>Annual % Growth</u>	<u>Average Initial Truck Factor (ESALs/Truck)</u>	<u>Annual % Growth in Truck Factor</u>	<u>Accumulated 80-kN ESALs over Performance Period</u>
1	98.5	2	0.0004	0	493
2	1	2	1.75	0	21,898
3	0.5	2	0.6	0	3,754
Total	100	-	-	-	26,145

Growth Compound

Total Calculated Cumulative ESALs 26,145

### Specified Layer Design

<u>Layer</u>	<u>Material Description</u>	<u>Struct Coef. (Ai)</u>	<u>Drain Coef. (Mi)</u>	<u>Thickness (Di)(mm)</u>	<u>Width (m)</u>	<u>Calculated SN (mm)</u>
1	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

### A Proprietary AASHTOWare Computer Software Product

#### Overlay Design Module

McClelland Road - Overlay Section  
ADT data from Corinth-Pittsburg Landing Rd = 345 (1995)  
CBR = 6

#### AC Overlay of AC Pavement

Structural Number for Future Traffic

50 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	19	31
Remaining Life	-	-
Non-Destructive Testing	-	-

#### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	63,972
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	62,055 kPa

Calculated Structural Number for Future Traffic 50 mm

#### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	75

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	19 mm
Calculated Effective Pavement Structural Number	19 mm

#### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	345
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %

Percent Trucks in Design Direction

100 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/ Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	1,206
2	1	2	1.75	0	53,580
3	0.5	2	0.6	0	9,185
Total	100	-	-	-	63,972

Growth

Compound

Total Calculated Cumulative ESALs

63,972

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	70	-	31
Total	-	-	-	70	-	31

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Overlay Design Module

Rhea Springs Road  
CBR = 7

### AC Overlay of AC Pavement

Structural Number for Future Traffic 39 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	25	14
Remaining Life	-	-
Non-Destructive Testing	-	-

### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	21,139
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	72,398 kPa

Calculated Structural Number for Future Traffic 39 mm

### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface	0.25	1	100

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	25 mm
Calculated Effective Pavement Structural Number	25 mm

### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	114
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %
Percent Trucks in Design Direction	100 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/ Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	399
2	1	2	1.75	0	17,705
3	0.5	2	0.6	0	3,035
Total	100	-	-	-	21,139
Growth			Compound		
Total Calculated Cumulative ESALs			21,139		

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

### A Proprietary AASHTOWare Computer Software Product

#### Overlay Design Module

Reconnoitering Road  
CBR=7

#### AC Overlay of AC Pavement

Structural Number for Future Traffic 39 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	27	12
Remaining Life	-	-
Non-Destructive Testing	-	-

#### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	21,139
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	72,398 kPa

Calculated Structural Number for Future Traffic 39 mm

#### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	80
2	Aggregate Base Course	0.1	1	65

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	27 mm
Calculated Effective Pavement Structural Number	27 mm

#### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	114
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %



Percent Trucks in Design Direction

100 %

<u>Vehicle Class</u>	<u>Percent of ADT</u>	<u>Annual % Growth</u>	<u>Average Initial Truck Factor (ESALs/Truck)</u>	<u>Annual % Growth in Truck Factor</u>	<u>Accumulated 80-kN ESALs over Performance Period</u>
1	98.5	2	0.0004	0	399
2	1	2	1.75	0	17,705
3	0.5	2	0.6	0	3,035
Total	100	-	-	-	21,139

Growth

Compound

Total Calculated Cumulative ESALs

21,139

## Specified Layer Design

<u>Layer</u>	<u>Material Description</u>	<u>Struct Coef. (Ai)</u>	<u>Drain Coef. (Mi)</u>	<u>Thickness (Di)(mm)</u>	<u>Width (m)</u>	<u>Calculated SN (mm)</u>
1	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare  
Computer Software Product

### Overlay Design Module

Eastern Corinth Road

CBR = 6

### AC Overlay of AC Pavement

Structural Number for Future Traffic

45 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	37	8
Remaining Life	-	-
Non-Destructive Testing	-	-

### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	31,986
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	62,055 kPa

Calculated Structural Number for Future Traffic 45 mm

### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	100
2	Aggregate Base Course	0.1	1	120

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	37 mm
Calculated Effective Pavement Structural Number	37 mm

### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	345
Number of Lanes in Design Direction	1

Percent of All Trucks in Design Lane  
Percent Trucks in Design Direction

100 %  
50 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/ Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	603
2	1	2	1.75	0	26,790
3	0.5	2	0.6	0	4,593
Total	100	-	-	-	31,986

Growth

Compound

Total Calculated Cumulative ESALs

31,986

### Specified Layer Design

Layer	Material Description	Struct Coef. ( $\Delta_i$ )	Drain Coef. ( $M_i$ )	Thickness ( $D_i$ )(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	40	-	18
Total	-	-	-	40	-	18

# 1997 AASHTO Pavement Design

## DARWin Pavement Design and Analysis System

### A Proprietary AASHTOWare Computer Software Product

#### Overlay Design Module

Hamburg-Savannah Road  
ADT = 345 (USED SAME ADT AS CORINTH-PITTSBURG)

#### AC Overlay of AC Pavement

Structural Number for Future Traffic 50 mm

<u>Design Method</u>	<u>Effective Existing Structural Number (mm)</u>	<u>Overlay Structural Number (mm)</u>
Component Analysis	20	30
Remaining Life	-	-
Non-Destructive Testing	-	-

#### Structural Number for Future Traffic

Future 18-kip ESALs Over Design Period	63,972
Initial Serviceability	4.2
Terminal Serviceability	2.2
Reliability Level	85 %
Overall Standard Deviation	0.49
Subgrade Resilient Modulus	62,055 kPa

Calculated Structural Number for Future Traffic 50 mm

#### Effective Pavement Thickness - Component Analysis Method

<u>Layer</u>	<u>Material Description</u>	<u>Structural Coefficient</u>	<u>Drainage Coefficient</u>	<u>Thickness (mm)</u>
1	HACP Surface Course	0.25	1	80
2	Aggregate Base Course	0.1	1	0

Milling Thickness 0 mm

#### Calculated Results

Calculated Pavement Structural Number Before Milling	20 mm
Calculated Effective Pavement Structural Number	20 mm

#### Future Rigorous ESAL Calculation

Performance Period (years)	20
Two-Way Traffic (ADT)	345
Number of Lanes in Design Direction	1
Percent of All Trucks in Design Lane	100 %

Percent Trucks in Design Direction

100 %

Vehicle Class	Percent of ADT	Annual % Growth	Average Initial Truck Factor (ESALs/ Truck)	Annual % Growth in Truck Factor	Accumulated 80-kN ESALs over Performance Period
1	98.5	2	0.0004	0	1,206
2	1	2	1.75	0	53,580
3	0.5	2	0.6	0	9,185
Total	100	-	-	-	63,972

Growth

Compound

Total Calculated Cumulative ESALs

63,972

### Specified Layer Design

Layer	Material Description	Struct Coef. (Ai)	Drain Coef. (Mi)	Thickness (Di)(mm)	Width (m)	Calculated SN (mm)
1	HACP Overlay	0.44	1	70	-	31
Total	-	-	-	70	-	31

## **APPENDIX H - Allowable Bearing Capacity and Settlement Calculations**

MADE BY K.M.DATE 5/1/00PROJECT SH-1502(1)

CHECKED BY \_\_\_\_\_

DATE \_\_\_\_\_

CALCULATIONS FOR

Small bridge foundation @ Reconnecting  
Road. ultimate Bearing CapacitySHEET NO. 1/3

- using Meyerhof's bearing capacity eqn. 1-

$$q_{ult} = c N_c s_c d_c + \bar{q} N_q s_q d_q + 0.5 \gamma B' N_\gamma s_\gamma d_\gamma \quad (1)$$


Based on the boring logs subsurface soils at the bridge site consist of silty sand & silty clay with SPT N-values ranging from 2 to 30 blows per 300 mm.

Average SPT N-value will be used = 6

∴ assume  $c = 0$  (cohesionless soils)

∴ from table 3-4

(Foundation analysis &amp; design)

@  $N = 6$  $\Rightarrow \phi = 28^\circ$  $\gamma = 17.6 \text{ kN/m}^3$ 

- Calculate shape &amp; depth factors:-

for  $\phi > 10^\circ$ 

$$s_q = s_\gamma = 1 + 0.1 K_p \frac{B}{L}$$

- Assume  $B = 1.5 \text{ m}$ ,  $L = 6.5 \text{ m}$  (one lane + Pedes.)

$$\therefore B/L = 0.23$$

$$K_p = \tan^2(45 + \frac{28}{2}) = 2.77$$

$$\therefore s_q = s_\gamma = 1 + 0.1 (2.77) (0.23) = 1.06$$

$$- d_q = d_\gamma = 1 + 0.2 \sqrt{K_p} \frac{D}{B}$$

$$D/B = \frac{0.76}{1.5} = 0.51$$

MADE BY km DATE \_\_\_\_\_PROJECT SM 11502(1)

CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_

CALCULATIONS FOR \_\_\_\_\_ SHEET NO. 2/3

$$d_f = d_v = 1 + 0.2 \sqrt{2.77} (0.51) = 1.17$$

From Table 4-4 (Bowels)  $N_q = 14.7$  &  $N_v = 11.2$   
 $\therefore$  Sub. in eq. (1) above

$$q_{ult.} = 17.6 * 0.76 * 14.7 * 1.06 * 1.17 +$$

$$0.5 * 17.6 * 1.5 * 11.2 * 1.06 * 1.17$$

$$= 243.86 + 183.35 = 427.21 \text{ kPa}$$

$$\therefore q_{all} = \frac{q_{ult.}}{FS} = \frac{427.21}{3} = 142.4 \text{ kPa}$$

(29711 lb/ft<sup>2</sup>)

use allowable bearing pressure of

$$142 \text{ kPa} \quad (\approx 2900 \text{ lb/ft}^2)$$

(7680)

Assuming no overburden

$$\therefore q_{all} = \frac{183.35}{3} = 61.1 \text{ kPa} (1270 \text{ lb/ft}^2)$$

In case of no overburden with a footing width of 1.5 m - the

$$\text{allowable bearing capacity} = 61 \text{ kPa} (1270 \text{ lb/ft}^2)$$

- Try  $B = 2.0 \text{ m} (6.5')$

$$\therefore B/L = 0.31$$

$$s_q = s_v = 1.09 ; d_q = d_v = 1.17$$

$$\therefore q_{ult} = 243.9 + 0.5 * 17.6 * 2.0 * 11.2 * 1.09 * 1.17$$

251.39



MADE BY km DATE \_\_\_\_\_

PROJECT Shil (S02(1))

CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_

CALCULATIONS FOR \_\_\_\_\_ SHEET NO. 313

$$q_{ult.} = 243.9 + 251.89 = 495.79 \text{ kPa}$$

$$q_{all} = \frac{495.79}{3} = 165.1 \text{ kPa (3446 lb/ft}^2\text{)}$$

- With  $B = 2.0 \text{ m}$  &  $D = 0.46 \text{ m}$

$$= q_{all} = 165.0 \text{ kPa (3400 lb/ft}^2\text{)}$$

- With  $B = 2.0$  &  $D = 0$

$$= q_{all} = 83. \text{ kPa (1700 lb/ft}^2\text{)}$$

- Try  $B = 2.5 \text{ m}$   
 $B/L = 0.38$

$$S_q = S_\gamma = 1.1; \quad \frac{d_q}{d_\gamma} = 1.1$$

$$= q_{ult} = 238 + 300.85 \\ = 538.85 \text{ kPa}$$

$$q_{all} = \frac{538.85}{3} = \underline{\underline{179.6 \text{ kPa (3750 lb/ft}^2\text{)}}}$$

No overburden;  $q_{all} = \frac{300.85}{3} = 100.3 \text{ kPa}$

MADE BY RSW DATE 5/10/08PROJECT SH-1L 502(1)

CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_

CALCULATIONS FOR Settlement SHEET NO. 4/4

using the method in AASHTO, 1996 to  
calculate settlement-

$$S_e = q_o \frac{(1 - \nu^2) \sqrt{A}}{E_s P_s} \quad (1)$$

From Table 4.4.7.2.2A  
for loose sand

$$\Rightarrow E_s = 600 ksf = 28729 \text{ KPa}$$

$$\nu = 0.3$$

From table 4.4.7.2.2B

B (m)	L (m)	L/B	P <sub>s</sub>	A (m <sup>2</sup> )
1.5	9.5	6.3	1.25	14.25
2.0	9.5	4.25	1.21	19.0
2.5	9.5	3.8	1.17	23.75

Sub. in eqn. (1)

$$\therefore S_e = 13.6 \pm 14 \text{ mm at } B = 1.5 \text{ m}$$

$$= 18.8 \pm 19 \text{ mm at } B = 2.0 \text{ m}$$

$$= 23.6 \pm 24 \text{ mm at } B = 2.5 \text{ m}$$